



TEST REPORT



Engineering recommendation G99

**BUREAU
VERITAS**

**Requirements for the connection of generation equipment in
parallel with public distribution networks**

Report reference number	PVGB2401WDG0057-2
Date of issue	2024-01-19
Total number of pages	101
Testing laboratory name	Bureau Veritas Shenzhen Co., Ltd. Dongguan Branch
Address	No. 96, Guantai Road (Houjie Section), Houjie Town, Dongguan City, Guangdong Province, 523942, People's Republic of China
Accreditation	 Certificate # 2951.01
Applicant's name	Jiangsu Hanchu Energy Technology Co., Ltd
Address	No. 588, Jinhui Road, Huishan District, Wuxi City, Jiangsu Province, China
Test specification	
Standard	G99/1-9:2022 A2-3 Tests for a Type A Inverter Connected Power Generating Modules
Certificate	Certificate of compliance
Test report form number	G99-1 VER.3
Master TRF	Dated 2022-11-01
Test item description	Photovoltaic (PV) and battery inverter
Trademark	
Model / Type	HESS-HY-T-12K, HESS-HY-T1-12K
<small>This report is governed by, and incorporates by reference, the Conditions of Testing as posted at the date of issuance of this report at http://www.bureauveritas.com/home/about-us/our-business/cps/about-us/terms-conditions/ and is intended for your exclusive use. Any copying or replication of this report to or for any other person or entity, or use of our name or trademark, is permitted only with our prior written permission. This report sets forth our findings solely with respect to the test samples identified herein. The results set forth in this report are not indicative or representative of the quality or characteristics of the lot from which a test sample was taken or any similar or identical product unless specifically and expressly noted. Our report includes all of the tests requested by you and the results thereof based upon the information that you provided to us. Measurement uncertainty is only provided upon request for accredited tests. Statements of conformity are based on simple acceptance criteria without taking measurement uncertainty into account, unless otherwise requested in writing. You have 60 days from date of issuance of this report to notify us of any material error or omission caused by our negligence or if you require measurement uncertainty; provided, however, that such notice shall be in writing and shall specifically address the issue you wish to raise. A failure to raise such issue within the prescribed time shall constitute your unqualified acceptance of the completeness of this report, the tests conducted and the correctness of the report contents.</small>	

Ratings.....:	HESS-HY-T-12K	HESS-HY-T1-12K
Max. input PV voltage [V]	1100	
Input PV voltage range [V].....:	200-950	200-950
Max. Input PV current [A].....:	2*20,0	3*16,0
Input Battery voltage range [V]	120-600	
Max. Battery current [A]	30,0	30,0
Output AC voltage [V][Grid]:	3L/N/PE, 230V, 50Hz	
Nominal Output AC current [A] [Grid]:	17,4	17,4
Max. Output AC current [A] [Grid]:.....:	19,2	19,2
Nominal Output power [kW] [Grid].....:	12,0	12,0
Max. Output power [kVA] [Grid].....:	12,0	12,0
Output AC voltage [V][EPS]:	3L/N/PE, 230V, 50Hz	
Nominal Output AC current [A] [EPS]:	17,4	17,4
Max. Output AC current [A] [EPS]::	19,2	19,2
Nominal Output power [kW] [EPS]:	12,0	12,0
Max. Output power [kVA] [EPS]	12,0	12,0

Testing Location	Bureau Veritas Shenzhen Co., Ltd. Dongguan Branch
Address	No. 96, Guantai Road (Houjie Section), Houjie Town, Dongguan City, Guangdong Province, 523942, People's Republic of China
Tested by (name and signature)	Ryan He 
Approved by (name and signature)	Ken Chan 
Manufacturer's name	Jiangsu Hanchu Energy Technology Co., Ltd
Manufacturer address	No. 588, Jinhui Road, Huishan District, Wuxi City, Jiangsu Province, China
Factory's name	AISWEI New Energy Technology (Yangzhong) Co., Ltd
Factory address	No.588 Gangxing Road, Economic Development Zone, 212200 Yangzhong, Jiangsu Province, P.R.China

Document History			
Date	Internal reference	Modification / Change / Status	Revision
2023-01-19	Ryan He	This is a copy report, the test results is based on the original test report PVGB2306WDG0281-2, issue by Bureau Veritas Shenzhen Co., Ltd. Dongguan Branch, dated on 2023-10-23.	0
Supplementary information:			

Test items particulars	
Equipment mobility	Permanent connection
Operating condition.....	Continuous
Class of equipment.....	Class I
Protection against ingress of water ...	IP66 according to EN 60529
Mass of equipment [kg]	Approx. 26kg for all model
Test case verdicts	
Test case does not apply to the test object	N/A
Test item does meet the requirement.....	P(ass)
Test item does not meet the requirement.....	F(ail)
Testing	
Date of receipt of test item.....	2023-03-23
Date(s) of performance of test.....	2023-03-23 to 2023-10-23
General remarks:	
<p>The test results presented in this report relate only to the object(s) tested. This document may be published or passed on in full only. Extraction of parts needs the written permission of Bureau Veritas Shenzhen Co., Ltd. Dongguan Branch.</p> <p>Conformity statements are decided in accordance with IEC GUIDE 115:2021 Procedure 2 (accuracy method), unless otherwise normatively specified or contractually agreed.</p> <p>"(see Annex #)" refers to additional information appended to the report. "(see appended table)" refers to a table appended to the report.</p> <p>Throughout this report a comma is used as the decimal separator.</p> <ul style="list-style-type: none"> • "P_n" for the nominal active power: $P_n = V_n \times I_n \times \cos \varphi_n$ (single-Phase); $P_n = \sqrt{3} V_n \times I_n \times \cos \varphi_n$ (three-Phase) • "P_m" for the momentary power • "(c)" for over-excited • "(i)" for under-excited 	

Active and reactive power:

The regarded system of the voltage and current vectors is the load view (Figure 2):

- if the inverter feeds to the grid the active power is measured with negative sign. For the sake of reading the document the measured active infeed power has a positive sign.




Figure 1

For the representation in quadrants, a power circle is chosen whose representation is compatible with mathematical representations of trigonometry and complex numbers (see Figure 2). Angles are counted positively counter-clockwise as in mathematics. The phase angle is defined as the angle from the current pointer to the voltage pointer. The current pointer is always in the real axis; the position of the voltage pointer corresponds to the apparent power and the phase angle.




Figure 2

The different operating states can be represented in quadrants I to quadrant IV. The quadrants are named in a counter-clockwise direction.

- Quadrant I: Ohmic inductive load (coil)
- Quadrant II: One active power supplying generation plant with simultaneous reactive power consumption
- Quadrant III: A generation plant supplying active and reactive power
- Quadrant IV: Ohmic-capacitive load (capacitor)

This Test Report consists of the following documents:

1. Test Results
2. Annex No. 1 – EMC report
3. Annex No. 2 – Pictures of the unit
4. Annex No. 3 – Test equipment list

Copy of marking plate:



Model: HESS-HY-T-12K

PV input	Max. PV input power	18000Wp
	Max. PV input voltage	d.c. 1100V
	MPP voltage range	d.c. 200-950V
	Max. PV input current	d.c. 2X20A
	Isc PV (absolute maximum)	d.c. 2X30A
Battery input	Max. charge/discharge power	12000W/12000W
	Battery voltage range	d.c. 120-600V
	Max. battery charge/discharge current	d.c. 30A/30A
	Battery type	LiFePO4
Grid output	Rated grid voltage	3/N/PE-400V
	Rated grid frequency	50Hz/60Hz
	Rated grid output apparent power	12000VA
	Max. grid output apparent power	12000VA
	Rated grid output current	17.4A
	Max. grid output current	19.2A
Grid input	Rated grid voltage	3/N/PE-400V
	Rated grid frequency	50Hz/60Hz
	Max. grid input apparent power	24000VA
	Max. grid input current	34.8A
EPS output	Rated output voltage	3/N/PE-400V
	Rated output frequency	50Hz/60Hz
	Rated output apparent power	12000VA
	Max. output apparent power	12000VA
	Rated output current	17.4A
General information	Adjustable cos(φ)	0.8ind...0.8cap
	Operating temperature range	-25...+60°C
	Inverter topology	Non-Isolated
	Ingress protection	IP66
	Protective class	I
	Overvoltage category	II(PV), III(MAINS)

Support DRMO



Jiangsu Hanchu Energy Technology Co.,LTD
 Web: www.hanchuess.com
 Add.: No.588,Jinhui Road,Huishan District ,Wuxi City,Jiangsu Province,China



SN: L1102A35F0025 CODE: frNGM3PK

532-100006-00

Made in China



Model: HESS-HY-T1-12K

PV input	Max. PV input power	18000Wp
	Max. PV input voltage	d.c. 1100V
	MPP voltage range	d.c. 200-950V
	Max. PV input current	d.c. 3X16A
	Isc PV (absolute maximum)	d.c. 3X24A
Battery input	Max. charge/discharge power	12000W/12000W
	Battery voltage range	d.c. 120-600V
	Max. battery charge / discharge current	d.c. 30A/30A
	Battery type	LiFePO4
Grid output	Rated grid voltage	3/N/PE-400V
	Rated grid frequency	50Hz/60Hz
	Rated grid output apparent power	12000VA
	Max. grid output apparent power	12000VA
	Rated grid output current	17.4A
	Max. grid output current	19.2A
Grid input	Rated grid voltage	3/N/PE-400V
	Rated grid frequency	50Hz/60Hz
	Max. grid input apparent power	24000VA
	Max. grid input current	34.8A
EPS output	Rated output voltage	3/N/PE-400V
	Rated output frequency	50Hz/60Hz
	Rated output apparent power	12000VA
	Max. output apparent power	12000VA
	Rated output current	17.4A
General information	Adjustable cos(φ)	0.8ind...0.8cap
	Operating temperature range	-25...+60°C
	Inverter topology	Non-Isolated
	Ingress protection	IP66
	Protective class	I
	Overvoltage category	II(PV), III(MAINS)

Support DRMO



Jiangsu Hanchu Energy Technology Co.,LTD
 Web: www.hanchuess.com
 Add.: No.588,Jinhui Road,Huishan District ,Wuxi City,Jiangsu Province,China



XXXXXXXXXXXXXXXXXXXX

532-100006-00

Made in China

General product information:

The unit converts DC voltage into AC voltage.

The unit is a three phases type inverter.

The DC input of unit can be supplied from PV array and batteries.

The input and output are protected by Varistors to Earth. The unit is providing EMC filtering at the output toward mains. The unit does not provide galvanic separation from input to output (transformerless). The output is switched off redundant by the high power switching bridge and a two relays. This assures that the opening of the output circuit will also operate in case of one error.

Description of the electrical circuit:

The internal control is redundant built. It consists of Microcontroller Main DSP (U519) and slave DSP (U536).

The Main DSP (U519) control the relays by switching signals; measures the PV voltage, PV current, Bus voltage, grid voltage, frequency, AC current with injected DC and the array insulation resistance to ground. In addition it tests the current sensors and the RCMU circuit before each start up.

The slave DSP (U536) is measures the grid voltage, grid frequency and residual current, also can switch off the relays independently, and communicate with Main DSP (U519) each other.

The current is measured by a current sensor. The AC current signal and the injected DC current signal are sent to the Main DSP (U519). The Main DSP (U519) tests and calibrates before each start up all current sensors.

The unit provides two relays in series in all output conductors. When single fault applied to one relay, alarm an error code in display panel, another redundant relay provides basic insulation maintained between the PV array and the mains. All the relays are tested before each start up.




Figure 3 – Block diagram

Differences of the models:

The differences between four models refer to below description and table.

Model HESS-HY-T-12K is basic model.

Model HESS-HY-T1-12K is almost same with the model HESS-HY-T-12K but with 3 PV trackers and 6 pole DC switch.

Model number	HESS-HY-T-12K	HESS-HY-T1-12K
PV tracker's number	2	3
EPS output terminal	With	With
DC switch's pole number	4	6

Hardware version: 270-100501-01;

Master Software version: V610-05001-01;

Slave Software version: V610-60015-00;

Safety version: V610-11022-01.


All tests were performed on HESS-HY-T-12K. Tests of the EUT of HESS-HY-T-12K not applicable for the models, HESS-HY-T1-12K were performed on the concerned models and a statement is given at the relevant test.


Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
A.7	Requirements for Type Testing Power Generating Modules		
	<p>This Annex describes methodologies for undertaking compliance verification for Type A Power Generating Modules. The Annex describes approaches which were originally intended for small Power Park Modules. Manufacturers are free to adapt techniques described in Annex B where this is more economic or efficient, provided the Type A performance requirements are fully demonstrated. The Forms provided in Annex A.2 should be used as a basis for demonstration of compliance.</p> <p>Annex A.7.1 Power Park Module Requirements.</p> <p>Annex A.7.2 Synchronous Power Generating Module Requirements.</p> <p>Annex A.7.3 Additional Technology Requirements.</p> <ul style="list-style-type: none"> • A.7.3.1. Domestic CHP • A.7.3.2. Photo-voltaic • A.7.3.3. Fuel Cells • A.7.3.4. Hydro • A.7.3.5. Wind • A.7.3.6. Electricity Storage devices <p>Annex A.7.1 relates to any Generating Unit that uses an Inverter (or Converter) as its means of connecting to the Distribution Network.</p> <p>Annex A.7.2 relates to any Synchronous Power Generating Module that during normal running operation is connected directly to the Distribution Network and has a Rated Capacity < 50 kW, although Manufacturers may choose to use these requirements for larger Type A Synchronous Power Generating Modules.</p> <p>For type testing any Generating Unit select either Annex A.7.1 or Annex A.7.2 as is most appropriate to the Generating Unit under test. Annex A.7.2 should also be used for asynchronous Generating Units that are not connected to the Distribution Network via an Inverter (ie induction Generating Units).</p> <p>The Generating Unit may also require additional technology type tests as identified in Annex A.7.3.</p> <p>Examples</p> <p>A Wind Turbine system using an Inverter (or Inverters) for connection is required to use Annex A.7.1 – “Common Power Park Module Requirements” and Annex</p> <p>A.7.3.5 – “Wind” Additional Technology</p>	<p>Test sample is a:</p> <p>A.7.1 Power Park Module</p> <p>A.7.3.2 Photovoltaic (Additional Power Generating Module Technology Requirements)</p>	P

Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	<p>Requirements.</p> <p>A Hydro system using an induction generator connected directly to the Distribution Network is suggested to use Annex A.7.2 – “Synchronous” and Annex A.7.3.4– “Hydro” Additional Technology Requirements.</p>		
A.7.1	Power Park Module Requirements		P
A.7.1.1	<p>Certification & Type Testing Generating Unit Requirements</p> <p>A.7.1 can apply to Power Park Modules or to individual Inverters and/or Generating Units if the functionality is included in each unit of a Power Park Module. Within this Section A.7.1 the term Power Park Module will be used but its meaning can be interpreted within A.7.1 to mean Power Park Module, Generating Unit or Inverter as appropriate.</p> <p>A.7.1 describes a methodology for obtaining type certification or type verification for a Power Park Module containing an Inverter. Typically, all interface functions are contained within the Inverter and in such cases it is only necessary to have the Inverter Type Tested. Alternatively, a package of specific separate parts of equivalent function may also be Type Tested.</p> <p>The Interface Protection shall satisfy the requirements of all of the following standards. Where these standards have more than one part, the requirements of all such parts shall be satisfied, so far as they are applicable.</p> <p>BS EN 61000 (Electromagnetic Standards)</p> <p>BS EN 60255 (Electrical Relays)</p> <p>BS EN 61810 (Electrical Elementary Relays)</p> <p>BS EN 60947 (Low Voltage Switchgear and Control gear)</p> <p>BS EN 61869 (Instrument Transformers: Additional requirements for current transformers)</p> <p>Currently there are no harmonised functional standards that apply to the Power Park Module’s Interface Protection. Consequently, in cases where power electronics is used for energy conversion along with any separate Interface Protection unit they will need to be brought together and tested as a complete Power Park Module as described in this EREC G99, and recorded in format similar to that shown in Form A2-3 (Annex A.2).</p> <p>Where the Interface Protection is physically integrated within the overall Power Park Module control system, the functionality of the Interface Protection unit should not be compromised by any</p>	<p>Considered.</p> <p>Test results see below.</p>	P


Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	<p>failure of other elements of the control system (fail safe). For a Full Type Tested Power Park Module the completed Power Park Module's Interface Protection shall not rely on interconnection using cables which could be terminated incorrectly on site ie the interconnections shall be made by non-reversible plug and socket which the Manufacturer has made and tested prior to delivery to site.</p> <p>Where Type Tested components are wired together on site, ie not using specifically designed plugs and sockets for the purpose, it will be necessary to prove that all wiring has been correctly terminated by proving the functions which rely on the wiring at the time of commissioning as detailed in paragraph 15.2 and Form A2-4 (Annex A.2).</p> <p>This Annex is primarily designed for the testing of three phase Power Park Modules. However, where practicable, a single phase, or split phase test may be carried out if it can be shown that it will produce the equivalent results.</p> <p>This Annex applies to Power Park Modules either with or without load management or Electricity Storage devices connected on the prime mover side of the Power Park Module.</p>		
A.7.1.2	<p>Type Verification Functional Testing of the Interface Protection</p> <p>Type Testing is the responsibility of the Manufacturer. This test will verify that the operation of the Power Park Module Interface Protection shall result:</p> <p>a) in the safe disconnection of the Power Park Module from the DNO's Distribution Network in the event that system parameters exceed the protection settings specified in Table 10.1; and</p> <p>b) in the Power Park Module remaining connected to the DNO's Distribution Network while Distribution Network conditions are:</p> <p>(1) within the envelope specified by the settings plus and minus the tolerances specified for equipment operation in Table 10.1; and</p> <p>(2) within the trip delay settings specified in Table 10.1.</p> <p>Wherever possible the type testing of a Power Park Module designed for a particular type of prime mover should be proved under normal conditions of operation for that technology (unless otherwise noted).</p>	<p>Considered.</p> <p>Test results see below.</p>	P
A.7.1.2.1	<p>Disconnection times</p> <p>The minimum trip time delay settings, for over / under voltage, over / under frequency and loss of</p>	<p>Considered.</p> <p>Test results see below.</p>	P


Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	<p>mains tests below, are presented in Table 10.1.</p> <p>For over / under voltage, over / under frequency and loss of mains tests, reconnection shall be checked as detailed below.</p>		
A.7.1.2.2	<p>Over / Under Voltage</p> <p>The Power Park Module shall be tested by operating in parallel with a variable AC test supply, see Figure A.7.1. Correct protection and ride-through operation shall be confirmed during operation of the Power Park Module. The set points for over and under voltage at which the Power Park Module disconnects from the supply will be established by varying the AC supply voltage.</p> <p>To establish the trip voltage, the test voltage should be applied in steps of $\pm 0.5\%$ or less, of the voltage setting for a duration that is longer than the trip time delay, for example 1 s in the case of a delay setting of 0.5 s starting at least 4 V below or above the setting. The test voltage at which this trip occurred is to be recorded. Additional tests just above and below the trip voltage should be undertaken to show that the test is repeatable and the figure at which a repeatable trip occurs should be recorded on the type verification test report Annex A.2-3.</p> <p>To establish the trip time, the test voltage should be applied starting from 4 V below or above the recorded trip voltage and should be changed to 4 V above or below the recorded trip voltage in a single step. The time taken from the step change to the Inverter tripping is to be recorded on the type verification test report Annex A.2-3.</p> <p>To establish correct ride-through operation, the test voltage should be applied at each setting ± 4 V and for the relevant times shown in the Table in Annex A.2-3.</p> <p>For example to test over voltage setting stage 1 which is required to be set at nominally 262.2 V the circuit should be set up as shown below and the voltage adjusted to 254.2 V. The Power Park Module should then be powered up to export a measurable amount of energy so that it can be confirmed that the Power Park Module has ceased to output energy. The variable voltage supply is then increased in steps of no more than 0.5% of nominal (1.15 V) maintaining the voltage for at least 1.5 s (trip time plus 0.5 s) at each voltage level. At each voltage level confirmation that the Power Park Module has not tripped after the time delay is required to be taken. At the voltage level at which a trip occurs then this should be recorded as the provisional trip voltage. Additional tests just below and if necessary just above the provisional trip voltage will allow the actual trip voltage to be</p>	<p>Considered.</p> <p>Test results see below.</p>	P


Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	<p>established on a repeatable basis. This value should be recorded. For the sake of this example the actual trip level is assumed to have been established as being 261 V. The variable voltage supply should be set to 257 V the Power Park Module set to produce a measurable output and then the voltage raised to 265 V in a single step. The time from the step change to the output of Power Park Module falling to zero should be recorded as the trip time.</p> <p>The Power Park Module then needs to operate at 4 V below the nominal over voltage stage 1 setting which is 258.2 V for a period of at least 2 s without tripping and while producing a measurable output. This can be confirmed as a no trip in the relevant part of Annex A.2-3. The voltage then needs to be stepped up to the next level of 269.7 V for a period of 0.98 s and then back to 258.2 V during which time the output of the relay should continue with no interruption though it may change due to the change in voltage, this can be recorded as a no trip for the second value. The step up and step down test needs to be done a second time with a max value of 277.7 V and with a time of 0.48 s. The Power Park Module is allowed to shut down during this period to protect its self as allowed by note 1 of Table 10.1, but it shall resume production again when the voltage has been restored to 258.2 V or it may continue to produce an output during this period. There is no defined time for resumption of production but it shall be shown that restart timer has not operated so it will begin producing again in less than 20 s.</p> <p>Note that this philosophy should be applied to the under voltage, over and under frequency, RoCoF and Vector shift stability tests which follow.</p> <p>Note:</p> <p>(1) The frequency required to trip is the setting ± 0.1 Hz</p> <p>(2) Measurement of operating time should be measured at a value of 0.3 Hz</p> <p>(suggestion – 2 x tolerance) above/below the setting to give "positive" operation</p> <p>(3) The "No trip tests" need to be carried out at the relevant values and times as shown in the table in Annex A.2-3 to ensure that the protection will not trip in error.</p> <div style="text-align: center;">  </div> <p>Figure A.7.1. Power Park Module test set up – over / under voltage</p>		
A.7.1.2.3	<p>Over / Under Frequency</p> <p>The Power Park Module shall be tested by operating in parallel with a low impedance, variable</p>	<p>Considered.</p> <p>Test results see below.</p>	P

Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	<p>frequency test supply system, see Figure A.7.2. Correct protection and ride-through operation should be confirmed during operation of the Power Park Module. The set points for over and under frequency at which the Power Park Module system disconnects from the supply will be established by varying the test supply frequency.</p> <p>To establish a trip frequency, the test frequency should be applied in a slow ramp rate of less than 0.1 Hzs-1 , or if this is not possible in steps of 0.05 Hz for a duration that is longer than the trip time delay, for example 1 s in the case of a delay setting of 0.5 s. The test frequency at which this trip occurred is to be recorded. Additional tests just above and below the trip frequency should be undertaken to show that the test is repeatable and the figure at which a repeatable trip occurs should be recorded on the type verification test report Annex A.2-3.</p> <p>To establish the trip time, the test frequency should be applied starting from 0.3 Hz below or above the recorded trip frequency and should be changed to 0.3 Hz above or below the recorded trip frequency in a single step. The time taken from the step change to the Power Park Module tripping is to be recorded on the type verification test report Annex A.2-3. It should be noted that with some loss of mains detection techniques this test may result in a faster trip due to operation of the loss of mains protection. There are two ways around this. Firstly the loss of mains protection may be able to be turned off in order to carry out this test. Secondly by establishing an accurate frequency for the trip a much smaller step change could be used to initiate the trip and establish a trip time. This may require the test to be repeated several times to establish that the time delay is correct.</p> <p>To establish correct ride-through operation, the test frequency should be applied at each setting ± 0.2 Hz and for the relevant times shown in the table in Annex A.2-3.</p> <div style="text-align: center;">  </div> <p>Figure A.7.2 Power Park Module test set up – over / under frequency</p>		
A.7.1.2.4	<p>Loss of Mains Protection</p> <p>The tests should be carried out in accordance with BS EN 62116 and a subset of results should be</p>	<p>Considered. Test results see below.</p>	P

Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	<p>recorded as indicated in the Protection – loss of mains test section of Annex A.2-3 Type Test Verification Report.</p> <p>Multi phase Power Park Modules should be operated at part load while connected to a network running at about 50 Hz and one phase only shall be disconnected with no disturbance to the other phases. The Power Park Module should trip within 1 s. The test needs to be repeated with each phase disconnected in turn while the other two phases remain in operation and the results recorded in the Type Test declaration.</p>		
A.7.1.2.5	<p>Re-connection</p> <p>The tests should be carried out in accordance with BS EN 62116 and a subset of results should be recorded as indicated in the Protection – loss of mains test section of Annex A.2-3 Type Test Verification Report.</p> <p>Multi phase Power Park Modules should be operated at part load while connected to a network running at about 50 Hz and one phase only shall be disconnected with no disturbance to the other phases. The Power Park Module should trip within 1 s. The test needs to be repeated with each phase disconnected in turn while the other two phases remain in operation and the results recorded in the Type Test declaration.</p>	<p>Considered.</p> <p>Test results see below.</p>	P
A.7.1.2.6	<p>Frequency Drift and Step Change Stability test.</p> <p>The tests will be carried out using the same circuit as specified in A.7.1.2.3 above and following confirmation that the Power Park Module has passed the under and over frequency trip tests and the under and over frequency stability tests.</p> <p>Four tests are required to be carried out with all protection functions enabled including loss of mains. For each stability test the Power Park Module should not trip during the test.</p> <p>For the step change test the Power Park Module should be operated with a measurable output at the start frequency and then a vector shift should be applied by extending or reducing the time of a single cycle with subsequent cycles returning to the start frequency. The start frequency should then be maintained for a period of at least 10 s to complete the test. The Power Park Module should not trip during this test.</p> <p>For frequency drift tests the Power Park Module should be operated with a measurable output at the start frequency and then the frequency changed in a ramp function at 0.95 Hzs⁻¹ to the end frequency. On reaching the end frequency it should be maintained for a period of at least 10 s. The Power</p>	<p>Considered.</p> <p>Test results see below.</p>	P

Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	<p>Park Module should not trip during this test.</p> <p>The results shall be recorded on the test sheet of Annex A.2-3.</p>		
A.7.1.3	<p>Limited Frequency Sensitive Mode – Over (LFSM-O)</p> <p>There are two possible approaches to demonstrating LFSM-O. The first to use the test set up of Figure A.7.2. The second approach can be used where it is possible to inject a frequency control signal into the Power Generating Module. The Manufacturer or Generator can choose which is the more appropriate test for the Power Generating Module.</p> <p>The test below uses the test set up of Figure A.7.2 to demonstrate LFSM-O using a variable frequency supply. The alternative approach is covered in A.7.2.4.</p> <p>The test should be carried out above 80% Registered Capacity and repeated at 40-60% Registered Capacity using the specific threshold frequency of 50.4 Hz and Droop of 10%.</p> <p>The Power Park Module should be tested at the following frequencies:</p> <p>Step a) 50.00 Hz \pm0.01 Hz Step b) 50.45 Hz \pm0.05 Hz Step c) 50.70 Hz \pm0.10 Hz Step d) 51.15 Hz \pm0.05 Hz Step e) 50.70 Hz \pm0.10 Hz Step f) 50.45 Hz \pm0.05 Hz Step g) 50.00 Hz \pm0.01 Hz</p> <p>The frequency at each step should be maintained for at least one minute as illustrated in Figure A.7.3 and the Active Power reduction in the form of a gradient determined and assessed for compliance with paragraph 11.2.3.</p>  <p>Figure A.7.3 Testing the Active Power feed-in of the Power Generating Module at over frequency</p> <p>The Droop should be determined from the</p>	<p>Considered.</p> <p>Test results see below.</p>	P


Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	measurements between 50.4 Hz and 51.15 Hz. The allowed tolerance for the frequency measurement shall be ± 0.05 Hz. The allowed tolerance for Active Power output measurement shall be $\pm 10\%$ of the required change in Active Power . The resulting overall tolerance range for a nominal 10% Droop is +2.8% and – 1.5%, ie a Droop less than 12.8% and greater than 8.5%.		
A.7.1.4	Power Quality		P
A.7.1.4.1	Harmonics The tests should be carried out as specified in BS EN 61000-3-12 and can be undertaken with a fixed source of energy at two power levels firstly between 45 and 55% and at 100% of Registered Capacity .	Considered. Test results see below.	P
A.7.1.4.2	Power Factor The test set up shall be such that the Power Park Module supplies full load to the DNO's Distribution Network via the Power Factor (pf) meter and the variac as shown below in Figure A.7.3. The Power Park Module Power Factor should be within the limits given in paragraph 11.1.5, for three test voltages 0.94 pu, 1 pu V ²⁸ and 1.1 pu V.  <p>NOTE 1: For reasons of clarity the points of isolation are not shown. NOTE 2: It is permissible to use a voltage regulator or tapped transformer to perform this test rather than a variac as shown.</p> <p>Figure A.7.3 Power Park Module test set up – Power Factor</p> <p>²⁸ For a LV connected Power Generating Module 1 pu V = 230 V</p>	Considered. Test results see below.	P
A.7.1.4.3	Voltage Flicker The voltage fluctuations and flicker emissions from the Power Park Module shall be measured in accordance with BS EN 61000-3-11 and the technology specific Annex A.7.3. The required maximum supply impedance should be calculated and recorded in the relevant part of Compliance Verification Report in Form A2-3 (Annex A.2).	Considered. Test results see below.	P
A.7.1.4.4	DC Injection The level of DC injection from the Power Park Module -connected prime mover in to the DNO's Distribution Network shall not exceed the levels specified in 9.4.6 when measured during operation at three levels, 10%, 55% and 100% of rating with a tolerance of $\pm 5\%$. The DC injection requirements can be satisfied by the installation of an isolation transformer on the AC side of an Inverter -connected Power Park Module . A declaration that an isolating transformer is fitted	Considered. Test results see below.	P


Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	can be made in lieu of the tests noted above.		
A.7.1.5	<p>Short Circuit Current Contribution</p> <p>Power Park Module connected Power Generating Module's generally have small short circuit fault contributions however DNOs need to understand the contribution that they make to system fault levels in order to determine that they can continue to safely operate without exceeding design fault levels for switchgear and other circuit components.</p> <p>The following type tests shall be carried out and the results noted in Annex A.2-3.</p>  <p>Figure A.7.4 Power Park Module short circuit test circuit</p>	<p>Considered.</p> <p>Test results see below.</p>	P
A.7.1.6	<p>Self-Monitoring - Solid State Disconnection</p> <p>Some Power Park Modules include solid state switching devices to disconnect from the DNO's Distribution Network. In this case paragraph 9.7.9 requires the control equipment to monitor the output stage of the Power Park Module to ensure that in the event of a protection initiated trip the output voltage is either disconnected completely or reduced to a value below 50 V AC. This shall be verified either by self-certification by the Manufacturer, or additional material shall be presented to the tester sufficient to allow an assessment to be made.</p>	<p>Considered.</p> <p>Test results see below..</p>	P
A.7.1.7	<p>Power Park Modules which include Electricity Storage</p> <p>This paragraph provides a method for demonstrating compliance with the optional performance characteristic as discussed in the foreword. The tests shall be carried out to demonstrate how the Power Park Module Active Power when acting as a load (ie replenishing its energy store) responds to changes in system frequency.</p> <p>In general, four tests are proposed, one set of two at Rated Import Capacity, and one set of two at 40% of Rated Import Capacity.</p> <p>In both cases the test is to reduce frequency from 50 Hz at 2 Hz^s⁻¹. In the first case the lower frequency reached will be 49.0 Hz and the second case the lower frequency will be 48.8 Hz.</p> <p>In all cases the response shall meet the requirements of 11.2.3.3.</p>	<p>Considered.</p> <p>Test results see below.</p>	P
A.7.2	Synchronous Power Generating Module Requirements (up to and including		N/A


Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	50 kW)		
A.7.2.1	<p>Certification & Type Testing Generating Unit Requirements</p> <p>This Annex describes a methodology for obtaining type certification or type verification for a Synchronous Power Generating Module in conjunction with Form A2-1. Other compliance requirements are detailed in Form A2-2 which may be used as an alternative to this Annex.</p> <p>The Interface Protection of the Synchronous Power Generating Module shall satisfy the requirements of all of the following standards. Where these standards have more than one part, the requirements of all such parts shall be satisfied, so far as they are applicable.</p> <ul style="list-style-type: none"> • BS EN 61000 (Electromagnetic Standards) • BS EN 60255 (Electrical Relays) • BS EN 61810 (Electrical Elementary Relays) • BS EN 60947 (Low Voltage Switchgear and Control gear) • BS EN 61869 (Instrument Transformers: Additional requirements for current transformers) <p>Currently there are no harmonised functional standards that apply to the Power Generating Module Interface Protection, therefore in order to achieve Type Tested status the Power Generating Module and any separate Interface Protection unit will require their functionality to be Type Tested as described in this Annex, and recorded in format similar to that shown in Annex A.2-1.</p> <p>Where the Interface Protection is physically integrated within the overall Power Generating Module control system, the functionality of the Interface Protection unit should not be compromised by any failure of other elements of the control system (fail safe). For a Fully Type Tested Power Generating Module the completed Power Generating Module's Interface Protection shall not rely on interconnection using cables which could be terminated incorrectly on site ie the interconnections shall be made by non-reversible plug and socket which the Manufacturer has made and tested prior to delivery to site.</p> <p>Where Type Tested components are wired together on site, ie not using specifically designed plugs and sockets for the purpose, it will be necessary to prove that all wiring has been correctly terminated by proving the functions which rely on the wiring at the time of commissioning as detailed in paragraph 15.2 and Form A2-4 (Annex A.2).</p>	No synchronous Power Generating Module	N/A

Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	<p>Wherever possible the type testing of a Power Generating Module utilising a particular type of prime mover should be proved under normal conditions of operation for that prime mover (unless otherwise noted).</p> <p>This Annex can also be used for asynchronous Generating Units that are not connected to the Distribution Network via an Inverter as appropriate.</p> <p>This Annex also applies to any Synchronous Power Generating Modules that are powered by stored energy (eg compressed air), but the requirement to demonstrate the LFSM-O will not be required.</p>		
A.7.2.2	<p>Type Verification Testing of the Interface Protection Functions</p> <p>Type verification testing is the responsibility of the Manufacturer. This test will verify that the operation of the Power Generating Module Interface Protection shall result:</p> <ol style="list-style-type: none"> 1. in the safe disconnection of the Power Generating Module from the DNO's Distribution Network in the event that the protection settings specified in Table 10.1 are exceeded; and 2. in the Power Generating Module remaining connected to the DNO's Distribution Network while network conditions are: <ol style="list-style-type: none"> a. within the envelope specified by the settings plus and minus the tolerances specified for equipment operation in Table 10.1; and b. within the trip delay settings specified in Table 10.1. <p>The Interface Protection may be incorporated into the Power Generating Module in which case it should be tested as part of the Power Generating Module. Alternatively, the constituent devices that form the Interface Protection may be discrete in which case the tests may be carried out on the discrete protection devices independently from the Power Generating Module.</p> <p>In either case it will be necessary to verify that a protection operation will disconnect the Power Generating Module from the DNO's Distribution Network.</p>	No synchronous Power Generating Module	N/A
A.7.2.2.1	<p>Disconnection times</p> <p>The minimum trip time delay settings, for over / under voltage, over / under frequency and loss of mains tests below, are presented in Table 10.1.</p> <p>For over / under voltage, over / under frequency and loss of mains tests, reconnection shall be checked</p>	No synchronous Power Generating Module	N/A

Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	<p>as detailed below.</p> <p>In some systems it may be safer and more convenient to test the trip delay time and the disconnection time separately. This will allow the trip delay time to be measured in a test environment (in a similar way as for a protection relay). The disconnection time can be measured in the Power Generating Module's normal operation, allowing accurate measurement with correct inertia and prime mover characteristics. This is permitted providing the total disconnection time does not exceed the value specified in Section 10.6.7.1. When measuring the disconnection time where the Interface Protection is included in the Power Generating Module, 5 s disconnections should be initiated, and the average time recorded.</p>		
A.7.2.2.2	<p>Over / Under Voltage</p> <p>The Interface Protection shall be tested by operating the Power Generating Module in parallel with a variable AC test supply, as an example see Figure A.7.5.</p> <p>Correct protection and ride-through operation shall be confirmed. The set points for over and under voltage at which the Interface Protection disconnects from the supply, will be established by varying the frequency of the AC supply voltage. The disconnect sequence should be initiated when the network conditions mean the protection should trip in accordance with the settings in Table 10.1, otherwise normal operation should continue.</p> <p>To establish the certified trip voltage, the test voltage should be applied in steps of $\pm 0.5\%$ or less of the voltage setting for a duration that is longer than the trip time delay, for example 1 s in the case of a delay setting of 0.5 s starting at least 4 V below or above the setting. Additional tests just above and below the trip voltage should be undertaken to show that the test is repeatable and the figure at which a repeatable trip occurs should be recorded on the type verification test report Annex A.2-1.</p> <p>To establish the certified trip time, the test voltage should be applied starting from 4 V below or above the certified trip voltage and should be changed to 4 V above or below the certified trip voltage in a single step. The time taken from the step change to the Power Generating Module tripping is to be recorded on the type verification test report Annex A.2-1.</p> <p>To establish correct ride-through operation, the test voltage should be applied at each setting ± 4 V and for the relevant times shown in the Table in Annex A.2-1.</p> <p>For example, to test over voltage setting stage 1</p>	No synchronous Power Generating Module	N/A



Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	<p>which is required to be set at nominally 262.2 V the circuit can be set up as shown below and the voltage adjusted to 254.2 V. In integrated designs where there is no separate way of establishing that the Power Generating Module is disconnected, the Power Generating Module should be powered up to export a measurable amount of energy so that it can be confirmed that the Power Generating Module has ceased to output energy. The variable voltage supply is then increased in steps of no more than 0.5% of nominal voltage (1.15 V) maintaining the voltage for at least 1.5 s (trip time plus 0.5 s) at each voltage level. At each voltage level confirmation that the Power Generating Module has not tripped after the time delay is required to be taken. At the voltage level at which a trip occurs then this should be recorded as the provisional trip voltage. Additional tests just below and if necessary just above the provisional trip voltage will allow the actual trip voltage to be established on a repeatable basis. This value should be recorded. For the sake of this example the actual trip level is assumed to have been established as being 261 V. The variable voltage supply should be set to 257 V the Power Generating Module set to produce a measurable output (if necessary) and then the voltage raised to 265 V in a single step. The time from the step change to the disconnection of the Power Generating Module, the output of the Power Generating Module falling to zero should be recorded as the trip time.</p> <p>To confirm that the protection does not trip before the required time, the test voltage should be applied at each setting $\pm 4V$ and for the relevant times shown in the table in Annex A.2-1.</p> <p>Test results should be recorded on the Test Sheet shown in Annex A.2-1</p>  <p>Figure A.7.5.- Power Generating Module test set up – over / under voltage</p>		
A.7.2.2.3	<p>Over / Under Frequency</p> <p>The Interface Protection shall be tested by operating the Power Generating Module in parallel with a low impedance, variable frequency test supply system,</p> <p>as an example, see Figure A.7.6. Correct protection and ride-through operation should be confirmed during the test. The set points for over and under</p>	No synchronous Power Generating Module	N/A




Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	<p>frequency at which the Interface Protection disconnects the test supply will be established by varying the test supply frequency.</p> <p>To establish a trip frequency, the test frequency should be applied in a slow ramp rate of less than 0.1 Hzs-1, or if this is not possible in steps of 0.05 Hz for a duration that is longer than the trip time delay, for example 1 s in the case of a delay setting of 0.5 s. The test frequency at which this trip occurred is to be recorded. Additional tests just above and below the trip frequency should be undertaken to show that the test is repeatable and the figure at which a repeatable trip occurs should be recorded on the type verification test report Annex A.2-1.</p> <p>To establish the trip time, the test frequency should be applied starting from 0.3 Hz below or above the recorded trip frequency and should be changed to 0.3 Hz above or below the recorded trip frequency in a single step. The time taken from the step change to the Power Generating Module tripping is to be recorded on the type verification test report Annex A.2-1. It should be noted that with some loss of mains detection techniques this test may result in a faster trip due to operation of the loss of mains protection and if possible the loss of mains protection should be turned off in order to carry out this test. Otherwise a much smaller step change should be used to initiate the trip and establish a trip time which may require the test to be repeated several times to establish that the time delay is correct.</p> <div style="text-align: center;">  </div> <p>Figure A.7.6. Power Generating Module test set up – over / under frequency</p>		
A.7.2.2.4	<p>Loss of Mains Protection</p> <p>The resonant test circuit specified as an option for this test has been designed to model the interaction of the Power Generating Module under test with the local load including multiple Power Generating Module's in parallel.</p> <p>The Power Generating Module output shall be connected to a network combining a resonant circuit with a Q factor of >0.5 and a variable load. The value of the load is to match the Power Generating Module output. To facilitate the test for LoM there shall be a switch placed between the test load/ Power Generating Module combination and the</p>	No synchronous Power Generating Module	N/A




Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	<p>DNO's Distribution Network, as shown in Figure A.7.7.</p>  <p>Figure A.7.7 Power Generating Module test set up - loss of mains</p> <p>The Power Generating Module is to be tested at three levels of the Power Generating Module's Registered Capacity: 10%, 55% and 100% and the results recorded on the test sheet of Annex A.2-1.</p> <p>For each test the load match is to be within $\pm 5\%$. Each test is to be repeated five times.</p> <p>Load match conditions are defined as being when the current from the Power Generating Module meets the requirements of the test load ie there is no export or import of supply frequency current to or from the DNO's Distribution Network.</p> <p>The tests will record the Power Generating Module's output voltage and frequency from at least 2 cycles before the switch is opened until the protection system operates and disconnects itself from the DNO's Distribution Network, or for 5 s whichever is the lower duration.</p> <p>The time from the switch opening until the protection disconnection occurs is to be measured and shall comply with the requirements in Table 10.1.</p> <p>Multi phase Power Generating Modules should be operated at part load while connected to a network running at about 50 Hz and one phase only shall be disconnected with no disturbance to the other phases. The Power Generating Module should trip within 1 s. The test needs to be repeated with each phase disconnected in turn while the other two phases remain in operation and the results recorded in the Type Test declaration.</p>		
A.7.2.2.5	<p>Re-connection</p> <p>Further tests will be carried out with the three test circuits above to check the Power Generating Module time- out feature prior to automatic network reconnection. This test will confirm that once the AC supply voltage and frequency have returned to within the stage 1 settings specified in Table 10.1 following an automatic protection trip operation there is a minimum time delay of 20 s before reconnection will be allowed.</p>	No synchronous Power Generating Module	N/A
A.7.2.2.6	<p>Frequency drift and vector shift stability test.</p>	No synchronous Power	N/A


Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	<p>The tests will be carried out using the same circuit as specified in A.7.2.2.3 above and following confirmation that the Power Generating Module has passed the under and over frequency trip and no trip tests.</p> <p>Four tests are required to be carried out with all protection functions enabled including loss of mains. For each stability test the Power Generating Module should not trip during the test.</p> <p>For the step change test the Power Generating Module should be operated with a measurable output at the start frequency and then a vector shift should be applied by extending or reducing the time of a single cycle with subsequent cycles returning to the start frequency. The start frequency should then be maintained for a period of at least 10 s to complete the test. The Power Generating Module should not trip during this test.</p> <p>For frequency drift tests the Power Generating Module should be operated with a measurable output at the start frequency and then the frequency changed in a ramp function at 0.95 Hzs-1 to the end frequency. On reaching the end frequency it should be maintained for a period of at least 10 s. The Power Generating Module should not trip during this test.</p> <p>The results shall be recorded on the test sheet of Annex A.2-1.</p>	Generating Module	
A.7.2.3	Power Output with Falling Frequency	No synchronous Power Generating Module	N/A
A.7.2.3.1	<p>The Generator will propose and agree a test procedure with the DNO, which will demonstrate how the Synchronous Power Generating Module Active Power output responds to changes in system frequency.</p> <p>The tests can be undertaken by the Synchronous Power Generating Module powering a suitable load bank, or alternatively using the test set up of Figure A.7.6.</p> <p>In both cases a suitable test could be to start the test at nominal frequency with the Synchronous Power Generating Module operating at 100% of its Registered Capacity.</p> <p>The frequency should then be set to 49.5 Hz for 5 minutes. The output should remain at 100% of Registered Capacity.</p> <p>The frequency should then be set to 49.0 Hz and once the output has stabilised, held at this frequency for 5 minutes. The Active Power output shall not be below 99% of Registered Capacity.</p> <p>The frequency should then be set to 48.0 Hz and</p>	No synchronous Power Generating Module	N/A



Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	<p>once the output has stabilised, held at this frequency for 5 minutes. The Active Power output shall not be below 97% of Registered Capacity.</p> <p>The frequency should then be set to 47.6 Hz and once the output has stabilised, held at this frequency for 5 minutes. The Active Power output shall not be below 96.2% of Registered Capacity.</p> <p>The frequency should then be set to 47.1 Hz and held at this frequency for 20 s.</p> <p>The Active Power output shall not be below 95.0% of Registered Capacity and the Synchronous Power Generating Module shall not trip in less than the 20s of the test.</p> <p>The Generator shall inform the DNO if any load limiter control is additionally employed.</p>		
A.7.2.4	<p>Synchronous Power Generating Modules which include Electricity Storage</p> <p>This paragraph provides a method for demonstrating compliance with the optional performance characteristic as discussed in the foreword. The tests shall be carried out to demonstrate how the Synchronous Power Generating Module Active Power when acting as a load (ie replenishing its energy store) responds to changes in system frequency.</p> <p>In general four tests are proposed, one set of two at Rated Import Capacity, and one set of two at 40% of Rated Import Capacity.</p> <p>In both cases the test is to reduce frequency from 50 Hz at 2 Hzs⁻¹. In the first case the lower frequency reached will be 49.0 Hz and the second case the lower frequency will be 48.8 Hz.</p> <p>In all cases the response shall meet the requirements of 11.2.3.3.</p>	No synchronous Power Generating Module	N/A
A.7.2.5	<p>Limited Frequency Sensitive Mode – Over (LFSM-O)</p> <p>The tests described in this Annex A.7.2.4 are also suitable for Type A Power Generating Modules > 50 kW.</p>	No synchronous Power Generating Module	N/A
A.7.2.5.1	<p>This paragraph is applicable to all Synchronous Power Generating Modules other than slow acting micro hydro Synchronous Power Generating Modules which should refer to paragraph A.7.2.4.2.</p> <p>Note that this test is also an alternative to the test in A.7.1.3.</p> <p>The two frequency response tests in Limited Frequency Sensitive Mode (LFSM) to demonstrate LFSM-O capability to a frequency injection as shown by Figures A.7.8 and Figures A.7.9 are to be</p>	No synchronous Power Generating Module	N/A

Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	<p>conducted at Registered Capacity (although a lower power output may be agreed with the DNO if site conditions preclude attaining Registered Capacity, such as an absence of adequate wind).</p> <p>There should be sufficient time allowed between tests for control systems to reach steady state. The injection signal should be maintained until the Active Power (MW) output of the Power Generating Module has stabilised. The DNO may require repeat tests should the tests give unexpected results.</p> <p>The frequency input and the expected Active Power response are illustrated for different periods from 0 s to 130 s in Figure A.7.8 for a step change in frequency and in Figures A.7.9 for a ramp change in frequency. This should be in accordance with Section 11.2.4 (a threshold frequency of 50.4 Hz and a Droop of 10%) and undamped oscillations should not occur after the step or ramp frequency change.</p> <p>Note for diagram purposes only a short interval is shown between the frequency increase and decrease for each test. In practice the return step or ramp can start any time after the output has stabilized after the first step or ramp.</p> <p>The response should commence within 2 s and shall be to the left of the red line (ie between the green line and the red line) and be as close to the green line as possible when following the frequency step or ramp. Note that the red line represents the 0.5% s⁻¹ specified in 11.2.4.1.</p>		
	 <p>Figure A.7.8(j): LFSM-O step response test – frequency injection</p>		
	 <p>Figure A.7.9(ii): LFSM-O step response test – target response and limits</p>		

Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	 <p>Figure A.7.9(iii): LFSM-O step response test – expansion of the allowed 2 s response delay (frequency increase)</p>  <p>Figure A.7.8(iv): LFSM-O step response test – expansion of the allowed 2 s response delay (frequency decrease)</p> <p>* This frequency step Δf will generally be +2.0 Hz unless an injection of this size causes a reduction in plant output that takes the operating point below Minimum Stable Operating Level in which case an appropriate injection should be calculated in accordance with the following:</p> <p>For example 1.5 Hz is needed to take an initial output of 100% to a final output of 70%. If the initial output is not 100% and the Minimum Stable Operating Level is not 70% then the injected step should be adjusted accordingly as shown in the example given below:</p> <p>Initial output 100% Minimum Stable Operating Level 70% Frequency controller Drop 10% Frequency to be injected = $(1.00 - 0.70) \times 0.1 \times 50 = 1.5\text{Hz}$</p>  <p>Figure A.7.10(i): LFSM-O ramp response test – frequency injection</p>		

Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	 <p>Figure A.7.10(ii): LFSM-O – target response and limits</p>  <p>Figure A.7.9(iii): LFSM-O ramp response test – expansion (frequency increase)</p>  <p>Figure A.7.9(iv): LFSM-O ramp response test – expansion (frequency decrease)</p>		
A.7.2.5.2	<p>This paragraph is applicable to slow acting micro hydro Synchronous Power Generating Modules.</p> <p>Recognising the significant engineering challenge of physically reducing the electrical energy exported from a slow acting micro hydro Power Generating Module, given the mechanical and hydraulic lags involved, the Generator may engineer an appropriate LFSM-O response by automatically switching in load banks to absorb the electrical energy, using frequency sensitive relays or control gear.</p> <p>A single frequency response step test (ie no ramp test) is required in Limited Frequency Sensitive Mode (LFSM) to demonstrate the LFSM-O capability in response to a frequency injection of 2.0 Hz/s for 1 s as shown by the Figures A.7.10 below. The test is to be conducted at Registered Capacity (although a lower power output may be agreed with the DNO if site conditions preclude attaining Registered Capacity, such as an absence of</p>	No synchronous Power Generating Module	N/A

Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	<p>adequate water flow rate). Similarly if the frequency step takes the operating point below the Minimum Stable Operating Level an alternative appropriate injection should be calculated that demonstrates LFSM-O across the range that is available without breaching the Minimum Stable Operating Level.</p> <p>There should be sufficient time allowed between the step up in frequency for control systems to reach steady state before the following step down in frequency. The injection signal should be maintained until the Active Power (MW) output of the Power Generating Module has stabilised. The DNO may require repeat tests should the tests give unexpected results.</p> <p>The frequency input and the expected Active Power response are illustrated below. This should be in accordance with Section 11.2.4. Undamped oscillations should not occur after the step frequency change.</p> <p>For both the step up and step down parts of the test the response should commence within 2 s and shall always be to the left of the red line and be as close as possible to the green line representing 10% Droop (unless some other Droop is desired by the Generator). It is permissible to be to the left of the 2% Droop line when the first load bank is switched in (or the final one switched out, ie the first one to be switched out) but the output must be to the right of the 2% Droop line by the time the frequency has reached 52.0 Hz (or returned to 50.0 Hz).</p>  <p>Figure A.7.10(j): LFSM-O step response test (frequency increase) for slow acting micro hydro</p>		

Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	 <p>Figure A.7.10(ii): LFSM-O step response test (frequency decrease) for slow acting micro hydro</p>		
A.7.2.6	Power Quality		N/A
A.7.2.6.1	Harmonics The tests should be carried out as specified in BS EN 61000-3-12 and can be undertaken with a fixed source of energy at two power levels firstly between 45 and 55% and at 100% of maximum export capacity.	No synchronous Power Generating Module	N/A
A.7.2.6.2	Power Factor The test set up shall be such that the Power Generating Module supplies full load to the DNO's Distribution Network via the Power Factor (pf) meter and the variac as shown below in Figure A.7.10. The Power Generating Module pf should be within the limits given in paragraph 11.1.5, for three test voltages 230 V –6%, 230 V and 230 V +10%.	No synchronous Power Generating Module	N/A
	 <p>NOTE 1. For reasons of clarity the points of isolation are not shown</p> <p>NOTE 2: It is permissible to use a voltage regulator or tapped transformer to perform this test rather than a variac as shown</p> <p>Figure A.7.10 Power Generating Module test set up – Power Factor</p>		
A.7.2.6.3	Voltage Flicker The voltage fluctuations and flicker emissions from the Generating Unit shall be measured in accordance with BS EN 61000-3-11 and technology specific annex. The required maximum supply impedance should be calculated and recorded in the Type Test declaration Annex A.2-1.	No synchronous Power Generating Module	N/A
A.7.3	Additional Power Generating Module Technology Requirements		P
A.7.3.1	Domestic CHP	No Domestic CHP.	N/A

Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	<p>or Domestic CHP Power Park Modules the type verification testing and Interface Protection requirements will be as per the requirements defined in Annex A.7.1.</p> <p>For Domestic CHP Synchronous Power Generating Modules the type verification testing and Interface Protection requirements will be as per the requirements defined in Annex A.7.2.</p>		
A.7.3.2	<p>Photovoltaic</p> <p>As all current Photovoltaic Power Park Modules will connect to the DNO's Distribution Network via an Inverter, the type verification testing and Interface Protection requirements will be as per the requirements defined in Annex A.7.1.</p>	Photovoltaic inverter	P
A.7.3.3	<p>Fuel Cells</p> <p>As all current Fuel Cell Power Generating Modules will connect to the DNO's Distribution Network via an Inverter, the type verification testing and Interface Protection requirements will be as per the requirements defined in Annex A.7.1.</p>	No fuel cell	N/A
A.7.3.4	<p>Hydro</p> <p>Hydro can be connected to the DNO's Distribution Network directly using induction or Synchronous Power Generating Modules or it can be connected by an Inverter.</p> <p>The common requirements for the generator technologies will apply to micro hydro in addition the following needs to be taken into consideration.</p> <p>Power Generating Modules with manually fixed output or where the output is fixed by controlling the water flow through the turbine to a steady rate, need to comply with the maximum voltage change requirements of BS EN 61000-3-2 but do not need to be tested for P_{st} or P_{lt}.</p> <p>Power Park Modules where the output is controlled by varying the load on the generator using the Inverter and which therefore produces variable output need to comply with the maximum voltage change requirements of BS EN 61000-3-2 and also need to be tested for P_{st} and P_{lt} over a period where the range of flows varies over the design range of the turbine with a period of at least 2 hours at each step with there being 10 steps from min flow to maximum flow. P_{st} and P_{lt} values to recorded and normalised as per the method laid down in Annex A.3.</p>	No Hydro	N/A
A.7.3.5	<p>Wind</p> <p>Wind turbines can be connected to the DNO's Distribution Network directly, typically using asynchronous induction generators, or using</p>	No wind	N/A

Engineering recommendation G99-1			
Clause	Requirement – Test	Result – Remark	Verdict
	<p>Inverters.</p> <p>For those connected via Inverters, the type verification testing and Interface Protection requirements shall be as specified in Annex A.7.1.</p> <p>For those connected directly to the DNO's Distribution Network, the type verification testing and Interface Protection requirements shall be as specified in Annex A.7.2.</p> <p>For wind turbines, flicker testing should be carried out during the performance tests specified in BS EN 61400-12. Flicker data should be recorded from wind speeds of 1 ms⁻¹ below cut-in to 1.5 times 85% of the rated power. The wind speed range should be divided into contiguous bins of 1ms⁻¹ centred on multiples of 1 ms⁻¹. The dataset shall be considered complete when each bin includes a minimum of 10 minutes of sampled data.</p> <p>The highest recorded values across the whole range of measurements should be used as inputs to the calculations described in BS EN 61000-3-11 to remove background flicker values. Then the required maximum supply impedance values can be calculated as described in Annex A.2-3. Note that occasional very high values may be due to faults on the associated HV network and may be discounted, though care should be taken to avoid discounting values which appear regularly.</p>		
A.7.3.6	<p>Electricity Storage Device</p> <p>Electricity Storage devices can be connected to the DNO's Distribution Network directly or using Inverters.</p> <p>For those connected via Inverters, the type verification testing and Interface Protection requirements shall be as specified in Annex A.7.1</p> <p>For those connected directly to the DNO's Distribution Network, the type verification testing and Interface Protection requirements shall be as specified in Annex A.7.2.</p> <p>The tests associated with any requirements which have been identified in Annex A4 as not being applicable to Electricity Storage devices can be considered to be excluded tests in this Annex A7.</p>	No storage device	N/A

G99-1
Test Results:
A2-3 - Compliance Verification Report for Type A
Inverter Connected Power Generating Modules

A.7.1.2 Type Verification Functional Testing of the Interface Protection (Functional safety - fault condition tests according DIN V VDE V 0124-100)								P
Test result: HESS-HY-T-12K								
ambient temperature [°C]:		25,0						
model/type of power supply:		DC:62150H-1000S AC:61512						
manufacturer of power supply:		Chroma						
rated markings of power supply:		DC:0-1000V, 15kW AC:0-300V, 18kW						
Component No.	Fault	Test condition		Test time	Fuse No.	Fault condition		Result
		AC	DC			AC	DC	
PCE input	Reversed	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W AC Output: 230Vac / 0A / 0W FID: Cannot start MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
PCE input	s-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W AC Output: 230Vac / 0A / 0W FID: PEC stop, Fault code 59. PV1 string current abnormal. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
PCE input	Over-voltage	--	DC 1100	10 min.	--	--	--	DC Input: 1100Vdc / 0A / 0W AC Output: 230Vac / 0A / 0W FID: PEC stop, Fault code 37. PV over voltage MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.

PCE input (only for multistring)	Different input MPP1: low input MPP2: high input	--	DC 850/ 420	10 min.	--	--	--	DC1 Input: 850Vdc / 7,5A / 6050W DC2 Input: 420Vdc / 15,5A / 6050W AC Output: 230Vac / 52A / 12kW FID: normal working. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
PCE output	Power over-feed (OCP & OTP function controlled by DSP / software is disable)	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W AC Output: 230Vac / 0A / 0W FID: PEC stop, Fault code 46. High DC bus. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
PCE output	Over-voltage (OVP function controlled by DSP / software is disable)	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W AC Output: 230Vac / 0A / 0W FID: PEC stop, Fault code 46. DC bus is to high. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
PCE output	s-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W AC Output: 230Vac / 0A / 0W FID: PEC stop, overcurrent protect. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
PCE output	Phase sequence or polarity incorrect	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W AC Output: 230Vac / 0A / 0W FID: PEC cannot work, fault AC voltage fault MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.

PCE output	A-Phase miswiring grid connection	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PEC cannot work, fault AC voltage fault. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
PCE cooling system failure	Fan locked (MF1) CN04	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 18,5A / 12100W. AC Output: 230Vac / 52,1A / 12kW. FID: Normal work. MT: Ambient=60°C, IGBT=75,3°C, Transformer=82°C, Inductance=86,8°C SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
PCE cooling system failure	Opening blocked CN101	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 18,5A / 12100W. AC Output: 230Vac / 52,1A / 12kW. FID: Normal work. MT: Ambient=60°C, Enclosure=75,3°C. SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
MCU or DPS processer failure								
DSP failure	+1.2V power supply disable C708 s-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: DSP reset. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.

DSP failure	+3.3V power supply disable C719 s-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: DSP reset. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
DSP failure reset 20-30%P								
Loss of control & Function fault								
IGBT PMW	Loss / failure (no power) C299 s-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
IGBT PMW	Loss / failure (no power) U124 pin 6 to Q121 G s-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. IGBT Q121, Q111 broke. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input type="checkbox"/> Yes / <input checked="" type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input type="checkbox"/> Yes / <input checked="" type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
IGBT PMW	Loss / failure (no driver) U124 pin 6 to Q121 G s-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 6. DC bus is to high. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
PV/DC voltage detector	Loss / failure R440 s-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 8. AC HCT failure MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.

PV/DC voltage detector	Loss / failure R112 o-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 37. PV over voltage. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
PV/DC current detector	Loss / failure U101 pin 11-12 s-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE cannot stop. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
BUS voltage detector	Loss / failure R186 o-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 6. DC bus is to high. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
Inverter voltage detector	Loss / failure C589 s-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 34. AC voltage out of range. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
Inverter voltage detector	Loss / failure R451 o-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 34. AC voltage out of range. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.

Grid/AC voltage detector	Loss / failure C643 s-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 34. AC voltage out of range. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
Grid/AC voltage detector	Loss / failure R717 o-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 34. AC voltage out of range. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
DC isolation device function check	Loss / failure C584 s-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 53. ISO check: before enable constant current, ISO voltage > 300mV. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
DC isolation device function check	Loss / failure R429 o-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 53. ISO check: before enable constant current, ISO voltage > 300mV. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.

DC isolation device function check	Loss / failure R429 o-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 53. ISO check: before enable constant current, ISO voltage > 300mV. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
Relay / Contact or function check (K1 s-c)	Loss / failure RY501 s-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 3. Relay check fail. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
Relay / Contact or function check (K1 o-c)	Loss / failure RY502 o-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 10. Device fault. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
Relay / Contact or function check (K2 s-c)	Loss / failure RY504 s-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 3. Relay check fail. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
Relay / Contact or function check (K2 o-c)	Loss / failure RY508 o-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 10. Device fault. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.

Relay / Contact or function check (K3 s-c)	Loss / failure RY507 s-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 3. Relay check fail. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
Relay / Contact or function check (K3 o-c)	Loss / failure RY510 o-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 10. Device fault. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
Relay / Contact or function check (K4 s-c)	Loss / failure RY513 s-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 3. Relay check fail. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
Relay / Contact or function check (K4 o-c)	Loss / failure RY515 o-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 10. Device fault. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
RCD/RCM function check	Loss / failure CT106 pin 1-5 s-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 36. GFCI failure. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.

RCD/RCM function check	Loss / failure R450 o-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 36. GFCI failure. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
Ambient temperature detector	Loss / failure NTC 102 s-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 174. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
Ambient temperature detector	Loss / failure NTC 102 o-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 174. Low air temperature. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
Heat-sink temperature detector	Loss / failure NTC 102 s-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 40. Over temperature in inverter. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
Heat-sink temperature detector	Loss / failure NTC 102 o-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. Fault code 40. Over temperature in inverter. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.

DC input BUS capacitor (390 µF)	C208 s-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: IGBT Q121, Q122, Q123, C208, C209, C210 broke, machine protection, no open fire, basic insulation after failure. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input type="checkbox"/> Yes / <input checked="" type="checkbox"/> No. NCD: <input type="checkbox"/> Yes / <input checked="" type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
IGBT (IGBT DS)	Q111 s-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: PCE stop. IGBT Q111, Q121 broke, machine protection, no open fire, basic insulation after failure. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input type="checkbox"/> Yes / <input checked="" type="checkbox"/> No. RO: <input type="checkbox"/> Yes / <input checked="" type="checkbox"/> No. NCD: <input type="checkbox"/> Yes / <input checked="" type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
PSDR board								
DC SPS unit +7V	Output s-c C433 s-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: No fault code, PCE stop. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
Power supply transformer	C435 s-c +12V s-c	--	DC 650	10 min.	--	--	--	DC Input: 650Vdc / 0A / 0W. AC Output: 230Vac / 0A / 0W. FID: No fault code, PCE stop. MT: N/A SD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. GD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. RO: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NCD: <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No. NH: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail. DST: <input checked="" type="checkbox"/> Pass/ <input type="checkbox"/> Fail.
FID	Fault Indication			MT		Max. Temperature		
SD	PCE Shut Down:			GD		Disconnection To Grid		
RO	Recovered to Operate after removing the single fault setting			NCD		No comp. or parts damaged		
NH	No hazards occurred			DST		Dielectric strength test		
s-c	short-circuited			o-c		open-circuited		
o-l	Over-load.							
The errors in the control circuit simulate that the safety is even under one error ensured.								
Addendum – Shutdown device								

Each active phase can be switched. (L and N)	Yes. In each line and neutral a Relay with min. 2,3 mm gab used.
If no galvanic separation between AC and DC (PV): Two relays in series on each active phase are necessary to fulfil the basic insulation or simple separation based on the PV working voltage.	Two relays in series on each active phase
<p>Note: The tests had been performed on the HESS-HY-T-12K are valid for the HESS-HY-T1-12K since it is almost same as in hardware and software.</p>	

Operating Range				P
Test result: HESS-HY-T-12K				
Setting values	Over-voltage [V]:	253,0		
	Under-voltage [V]:	195,5		
	Over-frequency [Hz]:	52,00		
	Under-frequency [Hz]:	47,50		
<ul style="list-style-type: none"> - Test 1: U = 195,5 V; f = 47,0 Hz; P = 1,00 Sn; $\cos\phi = 1$; at least 20 s - Test 2: U = 195,5 V; f = 47,5 Hz; P = 1,00 Sn; $\cos\phi = 1$; at least 90 mins - Test 3: U = 253,0 V; f = 51,5 Hz; P = 1,00 Sn; $\cos\phi = 1$; at least 90 mins - Test 4: U = 253,0 V; f = 52,0 Hz; P = 1,00 Sn; $\cos\phi = 1$; at least 15 mins - Test 5: U = 230,0 V; f = 50,0 Hz; P = 1,00 Sn; $\cos\phi = 1$; at least 90 mins - Test 6: U = 230,0 V; f = 50,0 to 50,5 Hz; RoCoF=1Hz/s; P = 1,00 Sn; $\cos\phi = 1$ 				
Test sequence	Voltage [V]	Frequency [Hz]	Output power [kW]	Cos ϕ [1]
Test 1	195,5	47,00	11,38	1,000
Test 2	195,5	47,50	11,38	1,000
Test 3	252,9	51,50	11,93	0,999
Test 4	252,9	52,00	11,91	0,999
Test 5	229,9	50,00	11,99	1,000
Test 6	229,9	50,00	11,98	1,000
<p>Note:</p> <p>During the tests the interface protection was disabled.</p> <p>Operation at reduced power is allowed during test 1 and test 2, equal to the maximum power that can be supplied on reaching the maximum output current limit ($P \geq 0,85 \text{ Sn}$).</p> <p>During the sequence of test 3 and test 4, automatic adjustment to reduce power in the case of over-frequency was disabled.</p> <p>The tests had been performed on the HESS-HY-T-12K are valid for the HESS-HY-T1-12K since it is almost same as in hardware and software.</p>				


A.7.1.2.2 Over / Under Voltage						P
These tests should be carried out in accordance with Annex A.7.1.2.2.						
Test result: HESS-HY-T-12K						
Phase 1						
Function	Setting		Trip test		No trip test	
	Voltage	Time delay	Voltage	Time delay	Voltage / time	Confirm no trip
U/V	184,0V (0,8 pu)	2,5s	184,7V	2,554s	188V / 5,0s	No trip
					180V / 2,45s	No trip
O/V stage 1	262,2V (1,14 pu)	1,0s	262,8V	1,020s	258,2V / 5,0s	No trip
O/V stage 2	273,7V (1,19 pu)	0,5s	273,4V	0,520s	269,7V / 0,95s	No trip
					277,7V / 0,45s	No trip
Phase 2						
Function	Setting		Trip test		No trip test	
	Voltage	Time delay	Voltage	Time delay	Voltage / time	Confirm no trip
U/V	184,0V (0,8 pu)	2,5s	184,3V	2,560s	188V / 5,0s	No trip
					180V / 2,45s	No trip
O/V stage 1	262,2V (1,14 pu)	1,0s	262,2V	1,001s	258,2V / 5,0s	No trip
O/V stage 2	273,7V (1,19 pu)	0,5s	273,3V	0,508s	269,7V / 0,95s	No trip
					277,7V / 0,45s	No trip
Phase 3						
Function	Setting		Trip test		No trip test	
	Voltage	Time delay	Voltage	Time delay	Voltage / time	Confirm no trip
U/V	184,0V (0,8 pu)	2,5s	184,3V	2,573s	188V / 5,0s	No trip
					180V / 2,45s	No trip
O/V stage 1	262,2V (1,14 pu)	1,0s	263,4V	1,022s	258,2V / 5,0s	No trip
O/V stage 2	273,7V (1,19 pu)	0,5s	274,4V	0,511s	269,7V / 0,95s	No trip
					277,7V / 0,45s	No trip

Note:


The total disconnection time for voltage and frequency protection, including the operating time of the disconnection device, shall be the time delay setting with a tolerance of, -0s + 0,1 s.
 The Voltage required to trip is the setting $\pm 3,45$ V. The time delay can be measured at a larger deviation than the minimum required to operate the protection. The No trip tests need to be carried out at the setting ± 4 V and for the relevant times as shown in the table above to ensure that the protection will not trip in error.

The tests had been performed on the HESS-HY-T-12K are valid for the HESS-HY-T1-12K since it is almost same as in hardware and software.


Under voltage(Phase 1)




Over voltage (Phase 1)




Over voltage stage 2(Phase 1)




Under voltage(Phase 2)










A.7.1.2.3 Over / Under Frequency These tests should be carried out in accordance with Annex A.7.1.2.3.	P
--	----------


Test result: HESS-HY-T-12K						
Function	Setting		Trip test		No trip test	
	Frequency	Time delay	Frequency	Time delay	Frequency / time	Confirm no trip
U/F stage 1	47,5Hz	20,0s	47,50Hz	20,092s	47,7Hz / 30s	No trip
U/F stage 2	47,0Hz	0,5s	47,00Hz	0,556s	47,2Hz / 19,5s	No trip
					46,8 Hz / 0,45s	No trip
O/F	52,0Hz	0,5s	52,00Hz	0,550s	51,8Hz / 120s	No trip
					52,2 Hz / 0,45s	No trip

Note:
The total disconnection time for voltage and frequency protection, including the operating time of the disconnection device, shall be the time delay setting with a tolerance of, -0s + 0,1 s.


For frequency trip tests the frequency required to trip is the setting $\pm 0,1$ Hz. In order to measure the time delay a larger deviation than the minimum required to operate the projection can be used. The “No trip tests” need to be carried out at the setting $\pm 0,2$ Hz and for the relevant times as shown in the table above to ensure that the protection will not trip in error.

The tests had been performed on the HESS-HY-T-12K are valid for the HESS-HY-T1-12K since it is almost same as in hardware and software.






A.7.1.2.4 Loss of mains protection according BS EN 62116 These tests should be carried out in accordance with BS EN 62116. Annex A.7.1.2.4. Load imbalance (real, reactive load) for test condition A (EUT output = 100%)										P
Test result: HESS-HY-T-12K										
Test conditions		Frequency: 50+/-0,1Hz $U_N=230\pm 3V_{ac}$ Distortion factor of chokes < 2% Quality =1								
Disconnection limit		0,5 s								
No	$P_{EUT}^{1)}$ (% of EUT rating)	Reactive load (% of Q_L in 6.1.d) ¹⁾	$P_{AC}^{2)}$ (% of nominal)	$Q_{AC}^{3)}$ (% of nominal)	$I_{AC}^{4)}$ [A]	P_{EUT} [kW per phase]	V_{DC} [V]	Q_f [1]	Run on Time [ms]	Remarks ⁵⁾
1	100	100	0	0	0,137	4,0	620,0	1,002	423,0	BL
4	100	100	-5	-5	--	4,0	620,0	1,026	253,5	IB
5	100	100	-5	0	--	4,0	620,0	1,053	254,0	IB
6	100	100	-5	+5	--	4,0	620,0	1,079	258,0	IB
7	100	100	0	-5	--	4,0	620,0	0,975	180,5	IB
8	100	100	0	+5	--	4,0	620,0	1,025	181,0	IB
9	100	100	+5	-5	--	4,0	620,0	0,928	317,5	IB
10	100	100	+5	0	--	4,0	620,0	0,952	251,5	IB
11	100	100	+5	+5	--	4,0	620,0	0,976	382,5	IB
Parameter at 0% per phase			L= 42,12mH		R= 13,23Ω		C= 240,81μF			
Indicate additional shut down time included in above results. (Disconnection device operation time)									20 ms	
Note: Note for technologies which have a substantial shut down time this can be added to the 0,5 seconds in establishing that the trip occurred in less than 0,5s. Maximum shut down time could therefore be up to 1,0 seconds for these technologies. RLC is adjusted to min. +/-1% of the inverter rated output power 1) P_{EUT} : EUT output power 2) P_{AC} : Real power flow at S1 in Figure 1. Positive means power from EUT to utility. Nominal is the 0 % test condition value. 3) Q_{AC} : Reactive power flow at S1 in Figure 1. Positive means power from EUT to utility. Nominal is the 0 % test condition value. 4) Fundamental of I_{AC} when RLC is adjusted. 5) BL: Balance condition, IB: Imbalance condition. Condition A: EUT output power $P_{EUT} = \text{Maximum}^{5)}$ EUT input voltage ⁶⁾ = >75% of rated input voltage range 6) Maximum EUT output power condition should be achieved using the maximum allowable input power. Actual output power may exceed nominal rated output. 7) Based on EUT rated input operating range. For example, If range is between X volts and Y volts, 75% of range = $X + 0,75 \times (Y - X)$. Y shall not exceed $0,8 \times \text{EUT maximum system voltage}$ (i.e., maximum allowable array open circuit voltage). In any case, the EUT should not be operated outside of its allowable input voltage range. The tests had been performed on the HESS-HY-T-12K are valid for the HESS-HY-T1-12K since it is almost same as in hardware and software.										




A.7.1.2.4 Loss of mains protection according BS EN 62116 These tests should be carried out in accordance with BS EN 62116. Annex A.7.1.2.4. Load imbalance (real, reactive load) for test condition A (EUT output = 50 % – 66 %)										P
Test result: HESS-HY-T-12K										
Test conditions		Frequency: 50+/-0,1Hz U _N =230+/-3Vac Distortion factor of chokes < 2% Quality =1								
Disconnection limit		0,5 s								
No	P _{EUT} ¹⁾ (% of EUT rating)	Reactive load (% of QL in 6.1.d) 1)	P _{AC} ²⁾ (% of nominal)	Q _{AC} ³⁾ (% of nominal)	I _{AC} ⁴⁾ [A]	P _{EUT} [kW per phase]	V _{DC} [V]	Q _f [1]	Run on Time [ms]	Remarks ⁵⁾
12	66	66	0	-5	--	2,64	480,0	0,975	218,5	IB
13	66	66	0	-4	--	2,64	480,0	0,980	221,0	IB
14	66	66	0	-3	--	2,64	480,0	0,985	225,5	IB
15	66	66	0	-2	--	2,64	480,0	0,990	256,5	IB
16	66	66	0	-1	--	2,64	480,0	0,995	312,5	IB
2	66	66	0	0	0,103	2,64	480,0	1,000	491,5	BL
17	66	66	0	1	--	2,64	480,0	1,005	325,0	IB
18	66	66	0	2	--	2,64	480,0	1,010	263,0	IB
19	66	66	0	3	--	2,64	480,0	1,015	247,0	IB
20	66	66	0	4	--	2,64	480,0	1,020	222,0	IB
21	66	66	0	5	--	2,64	480,0	1,025	194,5	IB
Parameter at 0% per phase			L= 63,81mH		R= 20,04Ω		C= 158,93μF			
Indicate additional shut down time included in above results. (Disconnection device operation time)									20 ms	
Note: RLC is adjusted to min. +/-1% of the inverter rated output power 1) P _{EUT} : EUT output power 2) P _{AC} : Real power flow at S1 in Figure 1. Positive means power from EUT to utility. Nominal is the 0 % test condition value. 3) Q _{AC} : Reactive power flow at S1 in Figure 1. Positive means power from EUT to utility. Nominal is the 0 % test condition value. 4) Fundamental of I _{AC} when RLC is adjusted. 5) BL: Balance condition, IB: Imbalance condition. Condition B: EUT output power P _{EUT} = 50 % – 66 % of maximum EUT input voltage ⁵⁾ = 50 % of rated input voltage range, ±10 % 6) Based on EUT rated input operating range. For example, If range is between X volts and Y volts, 50 % of range = X + 0,5 × (Y – X). Y shall not exceed 0,8 × EUT maximum system voltage (i.e., maximum allowable array open circuit voltage). In any case, the EUT should not be operated outside of its allowable input voltage range. The tests had been performed on the HESS-HY-T-12K are valid for the HESS-HY-T1-12K since it is almost same as in hardware and software.										



A.7.1.2.4 Loss of mains protection according BS EN 62116 These tests should be carried out in accordance with BS EN 62116. Annex A.7.1.2.4. Load imbalance (real, reactive load) for test condition A (EUT output = 25 % – 33 %)										P
Test result: HESS-HY-T-12K										
Test conditions		Frequency: 50+/-0,1Hz $U_N=230\pm 3V_{ac}$ Distortion factor of chokes < 2% Quality =1								
Disconnection limit		0,5 s								
No	$P_{EUT}^{1)}$ (% of EUT rating)	Reactive load (% of Q_L in 6.1.d) 1)	$P_{AC}^{2)}$ (% of nominal)	$Q_{AC}^{3)}$ (% of nominal)	$I_{AC}^{4)}$ [A]	P_{EUT} [kW per phase]	V_{DC} [V]	Q_f [1]	Run on Time [ms]	Remarks ⁵⁾
22	33	33	0	-5	--	1,32	312,0	0,975	205,5	IB
23	33	33	0	-4	--	1,32	312,0	0,980	206,0	IB
24	33	33	0	-3	--	1,32	312,0	0,985	216,0	IB
25	33	33	0	-2	--	1,32	312,0	0,990	236,5	IB
26	33	33	0	-1	--	1,32	312,0	0,995	244,5	IB
3	33	33	0	0	0,051	1,32	312,0	1,000	428,0	BL
27	33	33	0	1	--	1,32	312,0	1,005	422,5	IB
28	33	33	0	2	--	1,32	312,0	1,010	237,0	IB
29	33	33	0	3	--	1,32	312,0	1,015	235,5	IB
30	33	33	0	4	--	1,32	312,0	1,020	214,5	IB
31	33	33	0	5	--	1,32	312,0	1,025	202,5	IB
Parameter at 0% per phase		L= 127,63mH			R= 40,08Ω			C= 79,47μF		
Indicate additional shut down time included in above results. (Disconnection device operation time)									20 ms	
Note: RLC is adjusted to min. +/-1% of the inverter rated output power 1) P_{EUT} : EUT output power 2) P_{AC} : Real power flow at S1 in Figure 1. Positive means power from EUT to utility. Nominal is the 0 % test condition value. 3) Q_{AC} : Reactive power flow at S1 in Figure 1. Positive means power from EUT to utility. Nominal is the 0 % test condition value. 4) Fundamental of I_{AC} when RLC is adjusted. 5) BL: Balance condition, IB: Imbalance condition. Condition C: EUT output power $P_{EUT} = 25\% - 33\%$ ⁵⁾ of maximum EUT input voltage ⁶⁾ = <20 % of rated input voltage range 6) Or minimum allowable EUT output level if greater than 33 %. 7) Based on EUT rated input operating range. For example, If range is between X volts and Y volts, 20 % of range = $X + 0,2 \times (Y - X)$. Y shall not exceed $0,8 \times$ EUT maximum system voltage (i.e., maximum allowable array open circuit voltage). In any case, the EUT should not be operated outside of its allowable input voltage range. The tests had been performed on the HESS-HY-T-12K are valid for the HESS-HY-T1-12K since it is almost										

same as in hardware and software.

**Disconnection at P_{AC} 0% and Q_{AC} 0% reactive load and 33% nominal power
Disconnection at No. 3**



A.7.1.2.5 Re-connection				P
Test result: HESS-HY-T-12K				
Test should prove that the reconnection sequence starts after a minimum delay of 20 seconds for restoration of voltage and frequency to within the stage 1 settings of table 10.1.				
Under Voltage (188,0 V)				
Time delay setting		Measured delay		
60s		60,6s		
Over Voltage (258,2 V)				
Time delay setting		Measured delay		
60s		60,2s		
Under Frequency (47,6 Hz)				
Time delay setting		Measured delay		
60s		62,2s		
Over Frequency (51,9 Hz)				
Time delay setting		Measured delay		
60s		60,2s		
Checks on no reconnection when voltage or frequency is brought to just outside stage 1 limits of table 1.				
	At 266,2V	At 180,0V	At 47,4Hz	At 52,1Hz
Confirmation that the Power Generating Module does not re-connect	No reconnection	No reconnection	No reconnection	No reconnection
Note: The tests had been performed on the HESS-HY-T-12K are valid for the HESS-HY-T1-12K since it is almost same as in hardware and software.				

A.7.1.2.6 Frequency Drift and Step Change Stability test This test should be carried out in accordance with Annex A.7.1.2.6.				P
Test result: HESS-HY-T-12K				
	Start Frequency	Change	Test Time	Confirm no trip
Positive Vector Shift	49,5Hz	+50 degrees		No trip
Negative Vector Shift	50,5Hz	-50 degrees		No trip
Positive Frequency drift	49,0Hz – 51,0 Hz	+0,95Hz/sec	2,1s	No trip
Negative Frequency drift	51,0Hz – 49,0 Hz	-0,95Hz/sec	2,1s	No trip
Note:				
Four tests are required to be carried out with all protection functions enabled including loss of mains. For each stability test the Power Park Module should not trip during the test.				
For the step change test the Power Park Module should be operated with a measurable output at the start frequency and then a vector shift should be applied by extending or reducing the time of a single cycle with subsequent cycles returning to the start frequency. The start frequency should then be maintained for a period of at least 10 s to complete the test. The Power Park Module should not trip during this test.				
For frequency drift tests the Power Park Module should be operated with a measurable output at the start frequency and then the frequency changed in a ramp function at 0,95 Hzs ⁻¹ to the end frequency. On reaching the end frequency it should be maintained for a period of at least 10 s. The Power Park Module should not trip during this test.				
The tests had been performed on the HESS-HY-T-12K are valid for the HESS-HY-T1-12K since it is almost same as in hardware and software.				

<p>A.7.1.3 Limited Frequency Sensitive Mode – Over frequency test The test should be carried out using the specific threshold frequency of 50.4 Hz and Droop of 10%. This test should be carried out in accordance with Annex A.7.1.3.</p>	P
---	----------

Test result: HESS-HY-T-12K

1-min mean value [Hz]:	a) 50,00	b) 50,45	c) 50,70	d) 51,15	e) 50,70	f) 50,45	g) 50,00
------------------------	----------	----------	----------	----------	----------	----------	----------

1. Measurement a) to g): Active power output > 80% P_n


Frequency [Hz]:	50,00	50,45	50,70	51,15	50,70	50,45	50,00
P _{expected} [kW]:	N/A	11,88	11,28	10,20	11,28	11,88	N/A
P _{measured} [kW]:	11,96	11,83	11,23	10,16	11,24	11,84	11,98
$\Delta P_{measured} / P_M$ [%]:	N/A	-0,42	-0,42	-0,33	-0,33	-0,33	N/A

2. Measurement a) to g): Active power output 40% and 60% after freezing > 80% P_n


Frequency [Hz]:	50,00	50,45	50,70	51,15	50,70	50,45	50,00
P _{expected} [kW]:	N/A	5,88	5,28	4,20	5,28	5,88	N/A
P _{measured} [kW]:	6,02	5,96	5,36	4,28	5,36	5,96	11,97
$\Delta P_{measured} / P_M$ [%]:	N/A	0,67	0,67	0,67	0,67	0,67	N/A

Limit $\Delta P / P_{1min}$: + 10 % of P_M


Graph of Measurement 1.: Active power output > 80% P_n



Graph of Measurement 2.:Active power output 40% and 60% after freezing > 80% P_n



Graph of power gradient:



Test:

The test is conducted for two powers. First, the test must start at a power > 80% P_n ("Measurement 1"), and in a second test, for a power between 40% to 60% P_n ("Measurement 2"). In the second test, after freezing of the P_M, the available active power output must be increased to a value > 80% P_n, and after the network frequency of 50,4 Hz is fallen below, the rise of the active power gradient must be recorded.

Point g) must be held until the micro-generator is again feeding in with the active power output available.

Assessment criterion:

For $f = 50,4$ Hz, the value of the P_M active power currently being generated is "frozen".

a) For adjustable micro-generators when:

- 1) the active power reduces between measuring points b) and f) given above with the set gradient P_M per Hz for a increasing frequency (or rises for a frequency decreasing again).
- 2) the maximum active power gradient occurring in point is less than the configured maximum active power per minute
- 3) the reaction value of the setpoint determined by the gradient characteristic curve does not differ from P_n by more than $\pm 10\%$.
- 4) the settling time is equal or below 2 s with an intentional delay set to zero

b) For partly adjustable micro-generators

- 1) when they behave as in a) within their adjustment range, and
- 2) when, outside the adjustable range, the power fed in on leaving the adjustment range remains constant until shutdown. Shutdown must be no later than at 51,5 Hz.

Note:

The tests had been performed on the HESS-HY-T-12K are valid for the HESS-HY-T1-12K since it is almost same as in hardware and software.

A.7.1.4.1 Harmonic Current Emissions							P	
The test requirements are specified in Annex A.7.1.4.1.								
Generating Unit tested to BS EN 61000-3-12								
Test result: HESS-HY-T-12K								
Generating Unit rating per phase (rpp)				4,0 kW				
Harmonic order	At 45-55% of Registered Capacity 6,0 kW						Harmonic %	
	Measured Value (MV) in Amps			Measured Value (MV) in %			Limit in BS EN61000-3-12	
	L1	L2	L3	L1	L2	L3	1 phase	3 phase
1st	8,923	8,983	8,848	51,305	51,652	50,875	--	--
2nd	0,108	0,053	0,066	0,623	0,306	0,381	8,00	8,00
3rd	0,040	0,030	0,026	0,232	0,175	0,151	21,60	N/A
4th	0,139	0,132	0,141	0,797	0,761	0,808	4,00	4,00
5th	0,131	0,134	0,134	0,755	0,771	0,769	10,70	10,70
6th	0,010	0,005	0,007	0,059	0,030	0,042	2,67	2,67
7th	0,058	0,060	0,057	0,334	0,344	0,328	7,20	7,20
8th	0,058	0,051	0,062	0,335	0,295	0,357	2,00	2,00
9th	0,014	0,006	0,015	0,079	0,034	0,088	3,80	N/A
10th	0,030	0,033	0,029	0,173	0,188	0,169	1,60	1,60
11th	0,225	0,237	0,240	1,294	1,362	1,379	3,10	3,10
12th	0,007	0,005	0,005	0,038	0,030	0,029	1,33	1,33
13th	0,131	0,130	0,125	0,752	0,746	0,717	2,00	2,00
14th	0,016	0,015	0,018	0,091	0,087	0,104	N/A	N/A
15th	0,010	0,005	0,008	0,060	0,031	0,047	N/A	N/A
16th	0,028	0,031	0,028	0,162	0,177	0,163	N/A	N/A
17th	0,041	0,044	0,048	0,234	0,252	0,276	N/A	N/A
18th	0,006	0,005	0,005	0,036	0,031	0,030	N/A	N/A
19th	0,046	0,047	0,045	0,265	0,273	0,259	N/A	N/A
20th	0,022	0,026	0,023	0,127	0,147	0,132	N/A	N/A
21th	0,008	0,006	0,007	0,045	0,036	0,039	N/A	N/A
22th	0,016	0,016	0,016	0,094	0,094	0,092	N/A	N/A
23th	0,017	0,020	0,014	0,100	0,117	0,082	N/A	N/A
24th	0,006	0,006	0,006	0,036	0,035	0,034	N/A	N/A
25th	0,037	0,039	0,037	0,211	0,225	0,210	N/A	N/A
26th	0,019	0,020	0,020	0,111	0,113	0,116	N/A	N/A
27th	0,006	0,006	0,007	0,035	0,034	0,039	N/A	N/A
28th	0,028	0,028	0,026	0,158	0,162	0,149	N/A	N/A
29th	0,020	0,021	0,022	0,118	0,120	0,129	N/A	N/A
30th	0,005	0,006	0,006	0,031	0,034	0,032	N/A	N/A

A.7.1.4.1 Harmonic Current Emissions							P	
The test requirements are specified in Annex A.7.1.4.1.								
Generating Unit tested to BS EN 61000-3-12								
Test result: HESS-HY-T-12K								
Generating Unit rating per phase (rpp)				4,0 kW				
Harmonic order	At 45-55% of Registered Capacity 6,0 kW						Harmonic %	
	Measured Value (MV) in Amps			Measured Value (MV) in %			Limit in BS EN61000-3-12	
	L1	L2	L3	L1	L2	L3	1 phase	3 phase
31th	0,020	0,022	0,020	0,114	0,124	0,113	N/A	N/A
32th	0,020	0,021	0,023	0,114	0,118	0,131	N/A	N/A
33th	0,006	0,006	0,006	0,034	0,033	0,036	N/A	N/A
34th	0,017	0,017	0,018	0,100	0,099	0,101	N/A	N/A
35th	0,016	0,018	0,017	0,093	0,106	0,095	N/A	N/A
36th	0,005	0,005	0,005	0,030	0,029	0,031	N/A	N/A
37th	0,020	0,021	0,019	0,115	0,122	0,110	N/A	N/A
38th	0,013	0,012	0,013	0,072	0,071	0,075	N/A	N/A
39th	0,006	0,005	0,005	0,034	0,026	0,029	N/A	N/A
40th	0,014	0,013	0,014	0,081	0,074	0,079	N/A	N/A
41th	0,011	0,010	0,010	0,065	0,057	0,057	N/A	N/A
42th	0,004	0,005	0,005	0,024	0,027	0,026	N/A	N/A
43th	0,018	0,018	0,016	0,102	0,101	0,094	N/A	N/A
44th	0,011	0,011	0,011	0,063	0,065	0,065	N/A	N/A
45th	0,005	0,004	0,004	0,029	0,023	0,023	N/A	N/A
46th	0,013	0,015	0,013	0,076	0,085	0,077	N/A	N/A
47th	0,014	0,013	0,014	0,081	0,074	0,078	N/A	N/A
48th	0,004	0,004	0,004	0,022	0,024	0,025	N/A	N/A
49th	0,010	0,010	0,009	0,056	0,055	0,050	N/A	N/A
50th	0,012	0,013	0,013	0,070	0,074	0,075	N/A	N/A
THD_ [%]				2,136	2,098	2,132	23	13
PWHD_ [%]	--	--	--	3,265	3,396	3,314	23	22

Note:
The normalization current is 17,391A.

A.7.1.4.1 Harmonic Current Emissions								P	
The test requirements are specified in Annex A.7.1.4.1.									
Generating Unit tested to BS EN 61000-3-12									
Test result: HESS-HY-T-12K									
Generating Unit rating per phase (rpp)					4,0kW				
Harmonic order	At 100% of rated output power 12,0kW						Harmonic [%]		
	Measured Value (MV) in Amps			Measured Value (MV) in %			Limit in BS EN61000-3-12		
	L1	L2	L3	L1	L2	L3	1 phase	3 phase	
1st	17,614	17,685	17,544	101,280	101,686	100,877	--	--	
2nd	0,129	0,074	0,068	0,741	0,425	0,388	8,00	8,00	
3rd	0,035	0,032	0,023	0,204	0,182	0,133	21,60	N/A	
4th	0,124	0,120	0,125	0,715	0,691	0,720	4,00	4,00	
5th	0,168	0,169	0,170	0,964	0,974	0,978	10,70	10,70	
6th	0,009	0,005	0,006	0,054	0,031	0,037	2,67	2,67	
7th	0,058	0,060	0,058	0,332	0,343	0,333	7,20	7,20	
8th	0,023	0,026	0,025	0,130	0,149	0,143	2,00	2,00	
9th	0,013	0,005	0,014	0,077	0,029	0,082	3,80	N/A	
10th	0,057	0,052	0,057	0,330	0,299	0,327	1,60	1,60	
11th	0,225	0,237	0,232	1,291	1,363	1,335	3,10	3,10	
12th	0,008	0,005	0,006	0,044	0,027	0,036	1,33	1,33	
13th	0,327	0,328	0,322	1,883	1,884	1,849	2,00	2,00	
14th	0,026	0,022	0,026	0,150	0,127	0,151	N/A	N/A	
15th	0,005	0,005	0,009	0,029	0,028	0,051	N/A	N/A	
16th	0,015	0,016	0,013	0,087	0,093	0,075	N/A	N/A	
17th	0,110	0,115	0,116	0,635	0,662	0,666	N/A	N/A	
18th	0,005	0,005	0,005	0,030	0,026	0,027	N/A	N/A	
19th	0,104	0,104	0,098	0,598	0,597	0,565	N/A	N/A	
20th	0,030	0,027	0,027	0,174	0,153	0,153	N/A	N/A	
21th	0,006	0,005	0,005	0,035	0,027	0,031	N/A	N/A	
22th	0,035	0,036	0,035	0,199	0,205	0,199	N/A	N/A	
23th	0,049	0,046	0,049	0,279	0,262	0,282	N/A	N/A	
24th	0,005	0,005	0,005	0,030	0,028	0,031	N/A	N/A	
25th	0,051	0,054	0,051	0,293	0,310	0,292	N/A	N/A	
26th	0,021	0,022	0,017	0,123	0,126	0,098	N/A	N/A	
27th	0,006	0,006	0,005	0,036	0,034	0,028	N/A	N/A	
28th	0,031	0,030	0,030	0,177	0,175	0,175	N/A	N/A	
29th	0,030	0,026	0,026	0,170	0,149	0,148	N/A	N/A	
30th	0,006	0,006	0,007	0,033	0,033	0,038	N/A	N/A	

A.7.1.4.1 Harmonic Current Emissions								P	
The test requirements are specified in Annex A.7.1.4.1.									
Generating Unit tested to BS EN 61000-3-12									
Test result: HESS-HY-T-12K									
Generating Unit rating per phase (rpp)					4,0kW				
Harmonic order	At 100% of rated output power 12,0kW						Harmonic [%]		
	Measured Value (MV) in Amps			Measured Value (MV) in %			Limit in BS EN61000-3-12		
	L1	L2	L3	L1	L2	L3	1 phase	3 phase	
31th	0,045	0,046	0,044	0,256	0,267	0,253	N/A	N/A	
32th	0,020	0,024	0,024	0,114	0,139	0,139	N/A	N/A	
33th	0,007	0,006	0,006	0,041	0,034	0,033	N/A	N/A	
34th	0,015	0,015	0,016	0,087	0,087	0,091	N/A	N/A	
35th	0,014	0,016	0,019	0,082	0,089	0,111	N/A	N/A	
36th	0,006	0,006	0,006	0,033	0,037	0,033	N/A	N/A	
37th	0,021	0,022	0,022	0,121	0,125	0,124	N/A	N/A	
38th	0,026	0,027	0,026	0,151	0,157	0,150	N/A	N/A	
39th	0,006	0,006	0,006	0,032	0,032	0,033	N/A	N/A	
40th	0,026	0,026	0,027	0,148	0,152	0,154	N/A	N/A	
41th	0,024	0,027	0,030	0,140	0,157	0,170	N/A	N/A	
42th	0,006	0,007	0,006	0,034	0,041	0,034	N/A	N/A	
43th	0,040	0,043	0,039	0,232	0,248	0,225	N/A	N/A	
44th	0,010	0,008	0,011	0,055	0,049	0,063	N/A	N/A	
45th	0,008	0,006	0,006	0,046	0,035	0,036	N/A	N/A	
46th	0,021	0,022	0,022	0,122	0,125	0,129	N/A	N/A	
47th	0,031	0,028	0,029	0,179	0,164	0,167	N/A	N/A	
48th	0,006	0,006	0,006	0,036	0,034	0,036	N/A	N/A	
49th	0,027	0,027	0,024	0,155	0,154	0,135	N/A	N/A	
50th	0,029	0,028	0,030	0,165	0,163	0,171	N/A	N/A	
THD_ [%]	--	--	--	2,988	2,960	2,922	23	13	
PWHD_ [%]	--	--	--	5,942	6,020	5,938	23	22	

Note:
The normalization current is 17,391A.

A.7.1.4.1 Harmonic Current Emissions							P	
The test requirements are specified in Annex A.7.1.4.1.								
Generating Unit tested to BS EN 61000-3-12								
Test result: HESS-HY-T1-12K								
Generating Unit rating per phase (rpp)				4,0 kW				
Harmonic order	At 45-55% of Registered Capacity 6,0 kW						Harmonic %	
	Measured Value (MV) in Amps			Measured Value (MV) in %			Limit in BS EN61000-3-12	
	L1	L2	L3	L1	L2	L3	1 phase	3 phase
1st	8,874	8,934	8,799	51,025	51,371	50,592	--	--
2nd	0,108	0,053	0,068	0,622	0,303	0,388	8,00	8,00
3rd	0,040	0,031	0,027	0,232	0,179	0,153	21,60	N/A
4th	0,139	0,133	0,141	0,799	0,764	0,812	4,00	4,00
5th	0,131	0,134	0,134	0,754	0,770	0,768	10,70	10,70
6th	0,011	0,005	0,008	0,063	0,031	0,045	2,67	2,67
7th	0,059	0,061	0,058	0,337	0,348	0,331	7,20	7,20
8th	0,057	0,050	0,061	0,326	0,290	0,350	2,00	2,00
9th	0,014	0,006	0,016	0,080	0,035	0,090	3,80	N/A
10th	0,029	0,032	0,029	0,166	0,182	0,164	1,60	1,60
11th	0,225	0,237	0,240	1,292	1,361	1,377	3,10	3,10
12th	0,007	0,005	0,005	0,038	0,031	0,029	1,33	1,33
13th	0,133	0,132	0,127	0,764	0,758	0,728	2,00	2,00
14th	0,017	0,015	0,019	0,095	0,088	0,107	N/A	N/A
15th	0,010	0,005	0,008	0,059	0,030	0,048	N/A	N/A
16th	0,030	0,033	0,030	0,173	0,188	0,174	N/A	N/A
17th	0,044	0,047	0,052	0,253	0,271	0,297	N/A	N/A
18th	0,006	0,005	0,005	0,035	0,032	0,028	N/A	N/A
19th	0,043	0,044	0,042	0,244	0,254	0,243	N/A	N/A
20th	0,023	0,027	0,024	0,132	0,154	0,140	N/A	N/A
21th	0,008	0,006	0,007	0,046	0,036	0,038	N/A	N/A
22th	0,017	0,016	0,016	0,096	0,092	0,094	N/A	N/A
23th	0,018	0,021	0,015	0,106	0,122	0,084	N/A	N/A
24th	0,006	0,006	0,006	0,037	0,035	0,033	N/A	N/A
25th	0,038	0,040	0,037	0,216	0,228	0,215	N/A	N/A
26th	0,018	0,019	0,019	0,105	0,108	0,109	N/A	N/A
27th	0,006	0,006	0,006	0,037	0,034	0,037	N/A	N/A
28th	0,026	0,027	0,025	0,152	0,157	0,144	N/A	N/A
29th	0,021	0,020	0,022	0,119	0,118	0,129	N/A	N/A
30th	0,005	0,006	0,006	0,032	0,034	0,033	N/A	N/A

A.7.1.4.1 Harmonic Current Emissions							P	
The test requirements are specified in Annex A.7.1.4.1.								
Generating Unit tested to BS EN 61000-3-12								
Test result: HESS-HY-T1-12K								
Generating Unit rating per phase (rpp)				4,0 kW				
Harmonic order	At 45-55% of Registered Capacity 6,0 kW						Harmonic %	
	Measured Value (MV) in Amps			Measured Value (MV) in %			Limit in BS EN61000-3-12	
	L1	L2	L3	L1	L2	L3	1 phase	3 phase
31th	0,020	0,022	0,020	0,114	0,125	0,113	N/A	N/A
32th	0,019	0,020	0,022	0,107	0,112	0,124	N/A	N/A
33th	0,006	0,005	0,006	0,035	0,031	0,036	N/A	N/A
34th	0,018	0,017	0,018	0,101	0,099	0,101	N/A	N/A
35th	0,016	0,018	0,017	0,091	0,104	0,095	N/A	N/A
36th	0,005	0,005	0,005	0,029	0,030	0,030	N/A	N/A
37th	0,021	0,022	0,019	0,118	0,126	0,112	N/A	N/A
38th	0,013	0,013	0,014	0,074	0,074	0,079	N/A	N/A
39th	0,006	0,005	0,005	0,033	0,027	0,029	N/A	N/A
40th	0,014	0,013	0,014	0,079	0,075	0,079	N/A	N/A
41th	0,012	0,010	0,010	0,068	0,060	0,059	N/A	N/A
42th	0,004	0,005	0,005	0,025	0,027	0,026	N/A	N/A
43th	0,018	0,018	0,016	0,103	0,101	0,094	N/A	N/A
44th	0,012	0,012	0,012	0,068	0,067	0,069	N/A	N/A
45th	0,005	0,004	0,004	0,029	0,023	0,023	N/A	N/A
46th	0,013	0,015	0,014	0,076	0,086	0,079	N/A	N/A
47th	0,014	0,013	0,014	0,083	0,076	0,079	N/A	N/A
48th	0,004	0,004	0,004	0,024	0,025	0,025	N/A	N/A
49th	0,009	0,009	0,008	0,054	0,052	0,048	N/A	N/A
50th	0,012	0,013	0,013	0,070	0,073	0,075	N/A	N/A
THD_ [%]	--	--	--	2,142	2,106	2,141	23	13
PWHD_ [%]	--	--	--	3,294	3,409	3,334	23	22

Note:
The normalization current is 17,391A.

A.7.1.4.1 Harmonic Current Emissions							P	
The test requirements are specified in Annex A.7.1.4.1.								
Generating Unit tested to BS EN 61000-3-12								
Test result: HESS-HY-T1-12K								
Generating Unit rating per phase (rpp)				4,0kW				
Harmonic order	At 100% of rated output power 12,0kW						Harmonic [%]	
	Measured Value (MV) in Amps			Measured Value (MV) in %			Limit in BS EN61000-3-12	
	L1	L2	L3	L1	L2	L3	1 phase	3 phase
1st	17,580	17,638	17,502	101,087	101,416	100,637	--	--
2nd	0,134	0,080	0,071	0,772	0,459	0,408	8,00	8,00
3rd	0,034	0,033	0,022	0,194	0,189	0,126	21,60	N/A
4th	0,125	0,121	0,126	0,717	0,695	0,727	4,00	4,00
5th	0,153	0,155	0,155	0,880	0,889	0,893	10,70	10,70
6th	0,010	0,005	0,006	0,059	0,031	0,037	2,67	2,67
7th	0,073	0,075	0,074	0,422	0,433	0,423	7,20	7,20
8th	0,038	0,042	0,041	0,217	0,243	0,234	2,00	2,00
9th	0,012	0,005	0,011	0,070	0,026	0,066	3,80	N/A
10th	0,058	0,054	0,060	0,335	0,311	0,346	1,60	1,60
11th	0,240	0,252	0,247	1,382	1,450	1,423	3,10	3,10
12th	0,009	0,005	0,007	0,051	0,026	0,040	1,33	1,33
13th	0,334	0,332	0,329	1,919	1,911	1,893	2,00	2,00
14th	0,016	0,022	0,018	0,091	0,125	0,102	N/A	N/A
15th	0,006	0,005	0,011	0,033	0,028	0,062	N/A	N/A
16th	0,041	0,036	0,038	0,234	0,210	0,218	N/A	N/A
17th	0,120	0,126	0,120	0,688	0,724	0,692	N/A	N/A
18th	0,006	0,003	0,005	0,034	0,020	0,028	N/A	N/A
19th	0,207	0,204	0,202	1,188	1,175	1,160	N/A	N/A
20th	0,008	0,004	0,007	0,044	0,022	0,040	N/A	N/A
21th	0,005	0,005	0,008	0,029	0,030	0,048	N/A	N/A
22th	0,023	0,022	0,019	0,133	0,127	0,111	N/A	N/A
23th	0,011	0,017	0,017	0,065	0,099	0,095	N/A	N/A
24th	0,005	0,004	0,004	0,026	0,021	0,022	N/A	N/A
25th	0,083	0,085	0,081	0,477	0,489	0,465	N/A	N/A
26th	0,026	0,021	0,025	0,149	0,120	0,143	N/A	N/A
27th	0,004	0,006	0,005	0,024	0,035	0,030	N/A	N/A
28th	0,028	0,029	0,028	0,159	0,164	0,159	N/A	N/A
29th	0,049	0,047	0,051	0,281	0,270	0,294	N/A	N/A
30th	0,005	0,005	0,005	0,027	0,027	0,026	N/A	N/A

A.7.1.4.1 Harmonic Current Emissions								P	
The test requirements are specified in Annex A.7.1.4.1.									
Generating Unit tested to BS EN 61000-3-12									
Test result: HESS-HY-T1-12K									
Generating Unit rating per phase (rpp)					4,0kW				
Harmonic order	At 100% of rated output power 12,0kW						Harmonic [%]		
	Measured Value (MV) in Amps			Measured Value (MV) in %			Limit in BS EN61000-3-12		
	L1	L2	L3	L1	L2	L3	1 phase	3 phase	
31th	0,052	0,055	0,055	0,299	0,316	0,315	N/A	N/A	
32th	0,025	0,022	0,021	0,144	0,127	0,124	N/A	N/A	
33th	0,005	0,005	0,004	0,031	0,028	0,023	N/A	N/A	
34th	0,034	0,032	0,034	0,195	0,187	0,198	N/A	N/A	
35th	0,044	0,040	0,041	0,256	0,229	0,237	N/A	N/A	
36th	0,005	0,007	0,006	0,029	0,038	0,032	N/A	N/A	
37th	0,053	0,052	0,054	0,304	0,300	0,312	N/A	N/A	
38th	0,017	0,019	0,015	0,100	0,108	0,085	N/A	N/A	
39th	0,005	0,005	0,004	0,030	0,029	0,025	N/A	N/A	
40th	0,021	0,023	0,024	0,123	0,130	0,138	N/A	N/A	
41th	0,017	0,013	0,010	0,099	0,077	0,058	N/A	N/A	
42th	0,006	0,009	0,007	0,034	0,053	0,040	N/A	N/A	
43th	0,013	0,014	0,015	0,077	0,082	0,084	N/A	N/A	
44th	0,017	0,017	0,012	0,099	0,096	0,072	N/A	N/A	
45th	0,006	0,006	0,006	0,034	0,034	0,036	N/A	N/A	
46th	0,046	0,049	0,045	0,264	0,280	0,257	N/A	N/A	
47th	0,028	0,022	0,024	0,161	0,126	0,140	N/A	N/A	
48th	0,007	0,007	0,006	0,039	0,039	0,036	N/A	N/A	
49th	0,028	0,029	0,029	0,158	0,166	0,169	N/A	N/A	
50th	0,044	0,042	0,044	0,255	0,243	0,255	N/A	N/A	
THD_ [%]	--	--	--	3,279	3,239	3,203	23	13	
PWHD_ [%]	--	--	--	8,218	8,183	8,087	23	22	


Note:
The normalization current is 17,391A.

A.7.1.4.2 Power factor				P
The test requirements are specified in Annex A.7.1.4.2.				
Test result: HESS-HY-T-12K				
Output power	216,2 V	230,0 V	253,0 V	Measured at three voltage levels and at full output. Voltage to be maintained within $\pm 1.5\%$ of the stated level during the test.
20%	0,998	0,998	0,993	
50%	1,000	0,999	0,999	
75%	1,000	1,000	0,999	
100%	1,000	1,000	0,999	
Limit	>0,95	>0,95	>0,95	
<p>Note: The test set up shall be such that the Power Park Module supplies full load to the DNO's Distribution System via the power factor (pf) meter and the variac as shown below in figure A.7.3. The Power Park Module pf should be within the limits given in paragraph 11.1.5, for three test voltages 230 V – 6%, 230V and 230 V + 10%. The tests had been performed on the HESS-HY-T-12K are valid for the HESS-HY-T1-12K since it is almost same as in hardware and software.</p>				

A.7.1.4.3 Voltage Flicker								P	
The test requirements are specified in Annex A.7.1.4.3.									
Test result: HESS-HY-T-12K									
		Starting			Stopping			Running	
		d _{max}	d _c	d _(t)	d _{max}	d _c	d _(t)	P _{st}	P _{It} 2 hours
Measured values at test impedance	L1	0,716	0,185	0,000	0,716	0,185	0,000	0,134	0,123
Normalised to standard impedance	L1	0,716	0,185	0,000	0,716	0,185	0,000	0,134	0,123
Normalised to maximum impedance	L1	0,716	0,185	0,000	0,716	0,185	0,000	0,134	0,123
Measured values at test impedance	L2	0,578	0,183	0,000	0,578	0,183	0,000	0,130	0,120
Normalised to standard impedance	L2	0,578	0,183	0,000	0,578	0,183	0,000	0,130	0,120
Normalised to maximum impedance	L2	0,578	0,183	0,000	0,578	0,183	0,000	0,130	0,120
Measured values at test impedance	L3	0,549	0,195	0,000	0,549	0,195	0,000	0,139	0,125
Normalised to standard impedance	L3	0,549	0,195	0,000	0,549	0,195	0,000	0,139	0,125
Normalised to maximum impedance	L3	0,549	0,195	0,000	0,549	0,195	0,000	0,139	0,125
Limits set under BS EN 61000-3-11		4%	3,3%	3,3% 500ms	4%	3,3%	3,3% 500ms	1,0	0,65
Test impedance		R	0,240	Ω	XI	0,150	Ω		
		Z	0,283	Ω					
Standard impedance		R	0,240	Ω	XI	0,150	Ω		
		Z	0,283	Ω					
Maximum Impedance		R	0,240	Ω	XI	0,150	Ω		
		Z	0,283	Ω					
Test result: HESS-HY-T1-12K									
		Starting			Stopping			Running	
		d _{max}	d _c	d _(t)	d _{max}	d _c	d _(t)	P _{st}	P _{It} 2 hours
Measured values at test impedance	L1	0,720	0,186	0,000	0,720	0,186	0,000	0,136	0,124
Normalised to standard	L1	0,720	0,186	0,000	0,720	0,186	0,000	0,136	0,124

A.7.1.4.3 Voltage Flicker									P
The test requirements are specified in Annex A.7.1.4.3.									
impedance									
Normalised to maximum impedance	L1	0,720	0,186	0,000	0,720	0,186	0,000	0,136	0,124
Measured values at test impedance	L2	0,581	0,184	0,000	0,581	0,184	0,000	0,131	0,120
Normalised to standard impedance	L2	0,581	0,184	0,000	0,581	0,184	0,000	0,131	0,120
Normalised to maximum impedance	L2	0,581	0,184	0,000	0,581	0,184	0,000	0,131	0,120
Measured values at test impedance	L3	0,552	0,196	0,000	0,552	0,196	0,000	0,139	0,126
Normalised to standard impedance	L3	0,552	0,196	0,000	0,552	0,196	0,000	0,139	0,126
Normalised to maximum impedance	L3	0,552	0,196	0,000	0,552	0,196	0,000	0,139	0,126
Limits set under BS EN 61000-3-11		4%	3,3%	3,3% 500ms	4%	3,3%	3,3% 500ms	1,0	0,65
Test impedance	R	0,240	Ω	XI	0,150	Ω			
	Z	0,283	Ω						
Standard impedance	R	0,240	Ω	XI	0,150	Ω			
	Z	0,283	Ω						
Maximum Impedance	R	0,240	Ω	XI	0,150	Ω			
	Z	0,283	Ω						
Note									
For voltage change and flicker measurements the following formula is to be used to convert the measured values to the normalised values where the power factor of the generation output is 0,98 or above.									
Normalised value = Measured value*reference source resistance/measured source resistance at test point.									
Three phase units reference source resistance is 0,24 Ω									
Where the power factor of the output is under 0,98 then the Xi to R ratio of the test impedance should be close to that of the Standard impedance.									
The stopping test should be a trip from full load operation.									

A.7.1.4.4 DC injection				P
The test requirements are specified in Annex A.7.1.4.4.				
Test result: HESS-HY-T-12K				
Phase 1				
Test level power	10%	55%	100%	
Recorded DC value [mA]	29,1	29,0	28,5	
As % of rated AC current	0,17	0,17	0,16	
Limit	0,25% I _{ACrated}			
Phase 2				
Test level power	10%	55%	100%	
Recorded DC value [mA]	18,4	36,2	29,5	
As % of rated AC current	0,11	0,21	0,17	
Limit	0,25% I _{ACrated}			
Phase 3				
Test level power	10%	55%	100%	
Recorded DC value [mA]	10,7	24,2	21,1	
As % of rated AC current	0,06	0,14	0,12	
Limit	0,25% I _{ACrated}			
Sum of all Phases				
Tests are to be carried out at three defined power levels $\pm 5\%$. At 230 V a 12,0kW three phase Inverter has a current output of 52,174 A so DC limit is 130,434 mA. These tests should be undertaken in accordance with Annex A.7.1.4.4.				
The % DC injection ("as % of rated AC current" below) is calculated as follows:				
$\% \text{ DC injection} = \frac{\text{Recorded DC value in Amps}}{\text{Base current where the base current is the Registered Capacity (W) / V phase}}$ The % DC injection should not be greater than 0,25%.				
Test level power	10%	55%	100%	
Recorded DC value Sum [mA]	58,2	89,4	79,1	
As % of rated AC current	0,11	0,17	0,15	
Limit	0,25% I _{ACrated}			



Test result: HESS-HY-T1-12K

Phase 1

Test level power	10%	55%	100%
Recorded DC value [mA]	30,9	31,2	31,2
As % of rated AC current	0,18	0,18	0,18
Limit	0,25% I _{Crated}		

Phase 2

Test level power	10%	55%	100%
Recorded DC value [mA]	15,5	19,6	32,4
As % of rated AC current	0,09	0,11	0,19
Limit	0,25% I _{Crated}		

Phase 3

Test level power	10%	55%	100%
Recorded DC value [mA]	16,5	16,7	25,4
As % of rated AC current	0,09	0,10	0,15
Limit	0,25% I _{Crated}		


Sum of all Phases

Tests are to be carried out at three defined power levels $\pm 5\%$. At 230 V a 12,0kW three phase Inverter has a current output of 52,174 A so DC limit is 130,434 mA. These tests should be undertaken in accordance with Annex A.7.1.4.4.

The % DC injection ("as % of rated AC current" below) is calculated as follows:

% DC injection = Recorded DC value in Amps / Base current where the base current is the Registered Capacity (W) / V phase. The % DC injection should not be greater than 0,25%.

Test level power	10%	55%	100%
Recorded DC value Sum [mA]	62,9	67,5	89,0
As % of rated AC current	0,12	0,13	0,17
Limit	0,25% I _{Crated}		




Note:
The tests should be carried out on a single Generating Unit.

A.7.1.5 Short Circuit Current Contribution for Inverters					P
The test requirements are specified in Annex A.7.1.5.					
Test result: HESS-HY-T-12K					
For a directly coupled SSEG			For a Inverter SSEG		
Phase 1					
Parameter	Symbol	Value	Time after fault	Volts	Amps
Peak Short Circuit current	i_p	N/A	20ms	-28,7Vac	-22,65A
Initial Value of aperiodic current	A	N/A	100ms	27,8Vac	0,02A
Initial symmetrical short-circuit current*	I_k	N/A	250ms	-17,4Vac	0,00A
Decaying (aperiodic) component of short circuit current*	i_{DC}	N/A	500ms	-22,8Vac	-0,04A
Reactance/Resistance Ratio of source*	X/R	N/A	Time to trip	0,050s	In seconds
Phase 2					
Parameter	Symbol	Value	Time after fault	Volts	Amps
Peak Short Circuit current	i_p	N/A	20ms	28,0Vac	4,32A
Initial Value of aperiodic current	A	N/A	100ms	12,1Vac	0,07A
Initial symmetrical short-circuit current*	I_k	N/A	250ms	-27,8Vac	0,07A
Decaying (aperiodic) component of short circuit current*	i_{DC}	N/A	500ms	4,4Vac	0,00A
Reactance/Resistance Ratio of source*	X/R	N/A	Time to trip	0,050s	In seconds
Phase 3					
Parameter	Symbol	Value	Time after fault	Volts	Amps
Peak Short Circuit current	i_p	N/A	20ms	-10,2Vac	8,61A
Initial Value of aperiodic current	A	N/A	100ms	0,82Vac	-0,10A
Initial symmetrical short-circuit current*	I_k	N/A	250ms	-27,6Vac	0,10A
Decaying (aperiodic) component of short circuit current*	i_{DC}	N/A	500ms	9,6Vac	0,00A
Reactance/Resistance Ratio of source*	X/R	N/A	Time to trip	0,050s	In seconds
Note:					
<p>The values of voltage and current should be recorded for a period of up to 1 second when the changeover switch should be returned to the normal position. The voltage and current at relevant times shall be recorded in the type test report (Appendix A2-3) including the time taken for the Power Park Modul to trip. (It is expected that the Power Park Module will trip on either loss of mains or under voltage in less than 1 s). The tests had been performed on the HESS-HY-T-12K are valid for the HESS-HY-T1-12K since it is almost same as in hardware and software.</p>					


<p>A.7.1.6 Self Monitoring – Solid state Disconnection. The test requirements are specified in Annex A.7.1.6.</p>	<p>N/A</p>
<p>It has been verified that in the event of the solid state switching device failing to disconnect the SSEG, the voltage on the output side of the switching device is reduced to a value below 50 volts within 0,5 seconds.</p>	<p>N/A</p>
<p>Note: Unit do not provide solid state switching relays. In case the semiconductor bridge is switched off, then the voltage on the output drops to 0. In this case the relays on the output will also open (5.5.2.1 Functional safety to VDE 0124-100).</p>	

A.7.1.7	Power Park Modules which include Electricity Storage This test should be carried out in accordance with 11.2.3.3.		P
	Test 1: 100% rated import power, 50,00 Hz to 49,00 Hz with 2 Hzs ⁻¹		
	Start: 50 ± 0,01 Hz	End: 49,00 Hz	
Frequency [Hz]:	50,00	49,00	
Active power [kW]:	-11,74	-1,80	
Reactive Power [kVar]:	0,37	0,30	
	Test 2: 100% rated import power 50,00 Hz to 48,80 Hz with 2 Hzs ⁻¹		
	Start: 50 ± 0,01 Hz	End: 48,80Hz	
Frequency [Hz]:	50,00	48,80	
Active power [kW]:	-11,91	2,39	
Reactive Power [kVar]:	0,37	0,45	
	Test 3: 40% rated import power 50,00 Hz to 49,00 Hz with 2 Hzs ⁻¹		
	Start: 50 ± 0,01 Hz	End: 49,00 Hz	
Frequency [Hz]:	50,00	49,00	
Active power [kW]:	-4,78	5,20	
Reactive Power [kVar]:	0,32	0,37	
	Test 4: 40% rated import power 50,00 Hz to 48,80 Hz with 2 Hzs ⁻¹		
	Start: 50 ± 0,01 Hz	End: 48,80 Hz	
Frequency [Hz]:	50,00	48,80	
Active power [kW]:	-4,77	9,16	
Reactive Power [kVar]:	0,33	0,26	
Test:			
(a) When the frequency falls to 49,5 Hz the automatic response shall start;			
(b) The frequency response characteristic shall be within the shaded area of Figure 4;			
(c) If the Electricity Storage device is not capable of moving from an import level to an appropriate export level within 20 s of the frequency falling to 49,2 Hz, then it shall cease to import; and			
(d) If the Electricity Storage device has not achieved at least zero Active Power import when the frequency has reached 48,9 Hz it shall cease to import immediately.			

<p>A.7.1.7</p>	<p>Power Park Modules which include Electricity Storage</p> <p>This test should be carried out in accordance with 11.2.3.3.</p>	<p>P</p>
<div style="text-align: center;">  </div> <p>In general four tests are proposed, one set of two at rated import capacity, and one set of two at 40% of rated import capacity. In both cases the test is to reduce frequency from 50 Hz at 2 Hz^s⁻¹. In the first case the lower frequency reached will be 49,0 Hz and the second case the lower frequency will be 48,8 Hz.</p> <p>Note:</p> <p>The tests had been performed on the HESS-HY-T-12K are valid for the HESS-HY-T1-12K since it is almost same as in hardware and software.</p>		

A.7.2.3	Output Power with falling Frequency					P
Test result: HESS-HY-T-12K						
5-min mean value (each)	a)	b)	c)	d)	e)	f)
Frequency [Hz]:	50,00	49,50	49,00	48,00	47,60	47,10
Active power [kW]:	11,91	11,92	11,97	11,97	11,99	11,99
$\Delta P/P_{max}$ [%]:		-0,67	-0,25	-0,25	-0,08	-0,08

Graph of frequency a) to b) to c) to d) to e) to f):




Note:



For a CHP the test point a) at 50,00 Hz is taken as Registered capacity (P_{max}) due to limited discrete operating point of the CHP's thermal process.

Electronic inverter no power reduction take place.

The tests had been performed on the HESS-HY-T-12K are valid for the HESS-HY-T1-12K since it is almost same as in hardware and software.

Wiring functional tests: If required by para 15.2.1.	N/A
Confirm that the relevant test schedule is attached (test to be undertaken at time of commissioning)	N/A
Note: The inverter was tested in a test laboratory. The correct wiring functional test in the filed has to be done by the responsible person for the installation of the plant.	

<p>Cyber security, required by paragraph 9.1.7</p>	<p>P</p>
<p>Confirm that the Manufacturer or Installer of the Micro-generator has provided a statement describing how the Micro-generator has been designed to comply with cyber security requirements, as detailed in 9.1.7.</p>	<p>Yes</p>
<div style="display: flex; justify-content: space-between;"> <div style="width: 45%;"> <p style="text-align: center;">Jiangsu Hanchu Energy Technology Co.,Ltd</p> <hr/> <p style="text-align: center;">Manufacturer's declaration</p> <p>We, (Company: Jiangsu Hanchu Energy Technology Co.,Ltd, Address: No.588,Jinhui Road,Huishan District ,Wuxi City,Jiangsu Province,China) , hereby declare that all our below listed inverters comply with the cyber security requirements of the standard G99-1 and G98-1:</p> <ul style="list-style-type: none"> - Model no.: For G98-1: HESS-HY-T-05K, HESS-HY-T-06K, HESS-HY-T-08K, HESS-HY-T-10K, HESS-HY-T1-05K, HESS-HY-T1-06K, HESS-HY-T1-08K, HESS-HY-T1-10K, For G99-1: HESS-HY-T-12K, HESS-HY-T1-12K - Requirements listed in the standard(s): - ETSI EN 303 645; - relevant aspects of PAS 1879 "Energy smart appliances – Demand side response operation – Code of practice"; - relevant aspects of "Distributed Energy Resources – Cyber Security Connection Guidance" published by BEIS and the ENA; - Any other relevant standard that has been incorporated in the design of the Power Generating Module. <p style="text-align: center;"><small>Page 1 of 2</small></p> </div> <div style="width: 45%;"> <p style="text-align: center;">Jiangsu Hanchu Energy Technology Co.,Ltd</p> <hr/> <p>Declared by:</p> <p>Company name: Jiangsu Hanchu Energy Technology Co.,Ltd</p> <p>Responsible person: Allen Zhu</p> <p>Signature (and/or Stamp): </p> <p>Date: 2024.01.10</p> <p style="text-align: center;"><small>Page 2 of 2</small></p> </div> </div>	
<p>Note:</p> <p>Different levels of access, all are password protected, only certain parameters can be changed on maintenance level.</p>	

Logic Interface (input port) Required by paragraph 11.1.3.1	P
Confirm that an input port is provided and can be used to shut down the module.	Yes
Note: Manufacturer information provided.	
Provide high level description of logic interface, e.g. details in 11.1.3.1 such as AC or DC signal	Yes
<p>Logical interfaces are implemented by external devices (model: Ai-Logger 1000). COM1 or 2 or 3 of the external device is connected to COM0 of the power generation module (Figure 4 and Figure 5). Pins 1 and 10 of the DI port of the external device are connected to the switch or contactor. When the switch is closed, the generating module can work normally. When the switch is opened, the logical port has a DC voltage of 5V, and the power module reduces the active power to zero within 5 seconds.</p>	
	
Ai-Logger 1000	
	
Ai-Logger 1000 communication interface	




Figure 4 (For HESS-HY-T1-12K)




Figure 5 (For HESS-HY-T-12K)

Annex No. 1 EMC report



EMC TEST REPORT

REPORT NO.: BVKJ-ESH-P23121382B-1

MODEL NO.: Refer to model list

RECEIVED: Dec.21, 2023

ISSUED: Dec.27, 2023

APPLICANT: Jiangsu Hanchu Energy Technology Co.,Ltd

ADDRESS: No.588,Jinhui Road,Huishan District ,Wuxi
City,Jiangsu Province,China

ISSUED BY: BUREAU VERITAS ADT (Shanghai) Corporation

LAB LOCATION: No. 829, Xinzhuan Road, Shanghai, P.R.China
(201612)

This test report consists of 219 pages in total. It may be duplicated completely for legal use with the approval of the applicant. It should not be reproduced except in full, without the written approval of our laboratory. The test results in the report only apply to the tested item. The test results in this report are traceable to the national or international standards.



1 TEST PROGRAM

PRODUCT: Grid-connected hybrid Inverter

BRAND: 

MODEL NO.: Refer to model list

APPLICANT: Jiangsu Hanchu Energy Technology Co.,Ltd

TESTED: --

Emission : EN 62920 :2017+A11 :2020, EN 62920 :2017+A1 :2021

(IEC 62920 :2017+A1 :2021) ;

EN 61000-2-2 :2002+A1 :2017, EN 61000-2-2 :2002+A2 :2019

(IEC 61000-2-2 :2002+A1 :2017+A2 :2018) ;

EN61000-6-4 :2007+A1 :2011, EN IEC 61000-6-4 :2019(IEC 61000-6-4 :2018) ;

EN 61000-6-3 :2007+A1 :2011+AC :2012, EN IEC 61000-6-3 :2021(IEC 61000-6-3 :2020) ;

Standards : EN 55011 :2016+A1 :2017, EN 55011 :2016+A11 :2020, EN 55011 :2016+A2 :2021

(CISPR 11 :2015+A1 :2016+A2 :2019) ;

EN 61000-3-12 :2011 (IEC 61000-3-12 :2011+A1 :2021) ;

EN 61000-3-11 :2000, EN IEC 61000-3-11 : 2019 (IEC 61000-3-11 :2017) ;

EN 61000-3-2 :2014, EN IEC 61000-3-2 :2019+A1 :2021(IEC 61000-3-2 :2018+A1 :2020) ;

EN 61000-3-3 :2013+A1 :2019, EN 61000-3-3 :2013+A2 :2021,

EN 61000-3-3 :2013+A2 :2021+AC :2022 (IEC 61000-3-3 :2013+A1 :2017+A2 :2021)

Immunity : EN 62920 :2017+A11:2020, EN 62920 :2017+A1 :2021(IEC 62920:2017+A1:2021)

EN 61000-6-2 :2005+AC :2005, EN IEC 61000-6-2 :2019(IEC 61000-6-2 :2016) ;

EN61000-6-1 :2007, EN IEC 61000-6-1 :2019(IEC 61000-6-1 :2016) ;

(IEC 61000-4-2 :2008 ; IEC 61000-4-3 :2020 ; IEC 61000-4-4 :2012 ;

IEC 61000-4-5 :2014+A1 :2017 ; IEC 61000-4-6 :2013 ;

IEC 61000-4-8 :2009 ; IEC 61000-4-34 :2005+A1 :2009)

We, BUREAU VERITAS ADT (Shanghai) Corporation, declare that the equipment above has been tested and found compliance with the requirement limits of applicable standards. The test record, data evaluation and Equipment Under Test (EUT) configurations represented herein are true and accurate under the standards herein specified.

PREPARED BY : Yuan Zhang , DATE: Dec.27, 2023
Yuan ZHANG
Project Engineer

APPROVED BY : Sean Yu , DATE: Dec.27, 2023
Sean YU
RF Supervisor



3.4 TECHNICAL DATA SHEET

Model	HESS-HY-T -05K	HESS-HY-T -06K	HESS-HY-T -08K	HESS-HY-T -10K	HESS-HY-T -12K	
PV input	VMaxpv [Vdc]		1100			
	Iscpv [A]		30			
	MPP Voltage Range [Vdc]		150 - 950		200-950	
	Full Power MPP Voltage Range [Vdc]		250-850	290-850	350-850	380-850 450-850
	Max. Input Current [A]		20			
	Start PV Voltage [Vdc]		180			
	Back feed Current [A]		0			
	Overvoltage Category (OVC)		II			
Battery input	Battery voltage range[Vdc]		120 - 600			
	Max. charging / discharging power[kW]		5	6	8	10 12
	Battery voltage range@nominal power[Vdc]		200-600	210-600	270-600	340-600 400-600
	Max. charging current / Max. discharging current [A]		30			
Battery type		LiFePO4				
AC output	Rated Output Voltage [Vac]		220 / 380 V,230 / 400 V,240 / 415 ,3L/N/PE			
	Rated Output Frequency [Hz]		50 / 60			
	Rated Output Power [kW]		5	6	8	10 12
	Max.Apparent Power [kVA]		5.5	6.6	8.8	11.0 13.2
	Rated Output Current [A](@400V)		7.3	8.7	11.6	14.5 17.4
	Max.Output Current [A](@400V)		8.0	9.6	12.8	16.0 19.2
	Power Factor (cosφ)		1.0 (default). 0.80 lead. 0.80 lag			
	Overvoltage Category (OVC)		III			
AC input	Rated Input Voltage [Vac]		220 / 380 V,230 / 400 V,240 / 415 ,3L/N/PE			
	Rated Input Frequency [Hz]		50 / 60			
	Max. input power from grid [kW]		10	12	16	20 24
	Max. input current from grid[A]		14.5	17.4	23.2	29.0 34.8
EPS output	Nominal Output Voltage [Vac]		220 / 380 V,230 / 400 V,240 / 415 ,3L/N/PE			
	Nominal Output Frequency [Hz]		50 /60			
	Max. apparent power[kVA]		5	6	8	10 12
	Rated Current[A] (@400V)		7.3	8.7	11.8	14.5 17.4
SYSTEM	Protective Class		I			
	Enclosure Protection [IP]		IP66			
	Operating Temperature Range [°C]		-25 °C ... +60 °C			
	Pollution degree (PD)		PD 3			
	Max. operating altitude [m]		3000			
	Acoustic Noise [dB]		< 60			
	Weight [Kg]		24.5			
	Size (W / H / D) [mm]		545 / 485 / 205			
Firmware Version		Master DSP: 610-05001-00 Slave DSP: 610-60015-00 Safety: 610-11022-00				

1) For European market and Australian market, the max. apparent AC output power is equal to the rated power.



Model	HESS-HY-T1 -05K	HESS-HY-T1 -06K	HESS-HY-T1 -08K	HESS-HY-T1 -10K	HESS-HY-T1 -12K	
PV input	VMaxpv [Vdc]					1100
	Iscpv [A]					24
	MPP Voltage Range [Vdc]					150 - 950
	Full Power MPP Voltage Range [Vdc]		180~850V	200~850V	250~850V	320~850V
	Max. Input Current [A]					16
	Start PV Voltage [Vdc]					180
	Back feed Current [A]					0
	Overvoltage Category (OVC)					II
Battery input	Battery voltage range[Vdc]					120 - 600
	Max. charging / discharging power[kW]		5	6	8	10
	Battery voltage range@nominal power[Vdc]		200-600	210-600	270-600	340-600
	Max. charging current / Max. discharging current [A]					30
	Battery type					LiFePO4
AC output	Rated Output Voltage [Vac]					220 / 380 V,230 / 400 V,240 / 415 ,3L/N/PE
	Rated Output Frequency [Hz]					50 / 60
	Rated Output Power [kW]		5	6	8	10
	Max.Apparent Power [kVA]		5.5	6.6	8.8	11.0
	Rated Output Current [A](@400V)		7.3	8.7	11.6	14.5
	Max.Output Current [A](@400V)		8.0	9.6	12.8	16.0
	Power Factor (cosφ)					1.0 (default), 0.80 lead, 0.80 lag
AC input	Overvoltage Category (OVC)					III
	Rated Input Voltage [Vac]					220 / 380 V,230 / 400 V,240 / 415 ,3L/N/PE
	Rated Input Frequency [Hz]					50 / 60
	Max. input power from grid [kW]		10	12	16	20
	Max. input current from grid[A]		14.5	17.4	23.2	29.0
EPS output	Nominal Output Voltage [Vac]					220 / 380 V,230 / 400 V,240 / 415 ,3L/N/PE
	Nominal Output Frequency [Hz]					50 /60
	Max. apparent power[kVA]		5	6	8	10
	Rated Current[A] (@400V)		11.6	14.5	11.6	14.5
SYSTEM	Protective Class					I
	Enclosure Protection [IP]					IP66
	Operating Temperature Range [°C]					-25 °C ... +60 °C
	Pollution degree (PD)					PD 3
	Max. operating altitude [m]					3000
	Acoustic Noise [dB]					< 80
	Weight [Kg]					28
	Size (W / H / D) [mm]					545 / 465 / 205
	Firmware Version					Master DSP: 610-05001-00 Slave DSP: 610-60015-00 Safety: 610-11022-00

1) For European market and Australian market, the max. apparent AC output power is equal to the rated power.

Annex No. 2


Pictures of the unit

Photo of EUT


Enclosure front view



Enclosure back view



Enclosure left view




Enclosure right view



Enclosure top view




Enclosure bottom view-1 (For HESS-HY-T-12K)




Enclosure bottom view-2 (For HESS-HY-T1-12K)



Internal view-1 (For HESS-HY-T-12K)



Internal view-2 (For HESS-HY-T1-12K)



Annex No. 3 Test Equipment list

Date(s) of performance test: 2023-03-23 to 2023-10-23

Equipment	Internal No.	Manufacturer	Type	Serial No.	Next Calibration
Power Analyzer	A4080002DG	YOKOGAWA	WT3000	91M210852	Jul. 21, 2024
Power Analyser	A4080004DG	DEWESoft	SIRIUSI-HS-4xHV-4xLV	DB19104221	Jul. 21, 2024
AC Source	A7040019DG	Chroma	61512	61512000439	Monitored by Power Analyzer
DC Simulation Power Supply	A7040015DG	Chroma	62150H-1000S	62150EF00488	
	A7040016DG	Chroma	62150H-1000S	62150EF00490	
	A7040017DG	Chroma	620028	620028EF00120	
	A7040021DG	Chroma	62150H-1000S	62150EF00609	
	A7040022DG	Chroma	62150H-1000S	62150EF00595	
RLC Load	A7150027DG	Qunling	ACLT-3803H	93VOO2869	
Current transducer	A1060007DG	YOKOGAWA	CT200	1130700012	Jul. 16, 2024
	A1060008DG	YOKOGAWA	CT200	1130700017	Jul. 16, 2024
	A1060009DG	YOKOGAWA	CT200	1130700019	Jul. 16, 2024
	A10600010DG	YOKOGAWA	CT200	1130700016	Jul. 16, 2024
	A10600011DG	YOKOGAWA	CT200	1130700011	Jul. 16, 2024
	A10600012DG	YOKOGAWA	CT200	1130700018	Jul. 16, 2024
Eight Channel Digital Phosphor Oscilloscope	A4089017DG	YOKOGAWA	DL850	91N726247	Jul. 11, 2024
Oscilloscope probe	A1490008DG	YOKOGAWA	701901	//	Jul. 18, 2024
Oscilloscope probe	A1490009DG	YOKOGAWA	701901	//	Jul. 18, 2024
Oscilloscope probe	A1490010DG	YOKOGAWA	701901	//	Jul. 18, 2024
Oscilloscope probe	A1490011DG	YOKOGAWA	701901	//	Jul. 18, 2024
Temp. & Humi. Recorder	A7440034DG	HUATO	S580-TH	HT20103923	Jan. 31, 2024

--End of Test Report--